

6

030373

15-137-20309-00-00

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-

SE, SEC. 1, T. 5 S, R. 22 WE

1420 feet from N S section line

360 2280 feet from WE section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9988

Lease Name Boys Well # A-5

Operator: HYLAND HOLLAND OIL & GAS

County NORTON 113.52

Name & Address 3739 PALMER PARK BLVD.

Well Total Depth 3493 feet

228 N. Cascade Ave COLO. SPRINGS, COLORADO

Conductor Pipe: Size _____ feet

Suite 100 8090

Surface Casing: Size 8 5/8 feet 256' cwc 1654'

Colo. Spring, Colo. 80903

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor NICHOLAS CASING INC. License Number 6698

Address Box 108 Box 373 GENESEO KANSAS 67444

Company to plug at: Hour: AM Day: 27 Month: 12 Year: 19 84

Plugging proposal received from ALLEN NICHOLAS

(company name) NICHOLAS CASING PULLING INC. (phone) _____

were: 4 1/2 s/c @ 3421 w/200sf. w/BAILER DUMP 4SX.COM.CEM. ON BOTTOM - DUMP SAND TO 3300' - w/BAILER DUMP 4SX.COM.CEM. ON SAND. SHOOT OFF AND RECOVER PIPE. - RECOVERED 2520' OF 4 1/2" CASING.

Call for Top plug. Order 170sf 5450pcf 6% gel 3% cc - 40 sf gel 4 sf Hulle (400#) 1-8 5/8

wiper plug - 120 BBL water. - Perf @ 3362-57 / 3360-66 PBTD 3415

Bottom Plug by Marion

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 11:40AM Day: 27 Month: 12 Year: 19 84

ACTUAL PLUGGING REPORT Bottom Plug 4sx.com.cem w/bailer on PBTD @ 3415 - Sand to 3300' - w/bailer

4sx.com.cem. on top of sand. Top Plug Pumped down 8 5/8 w/4sx Hulle mix with 33sf

gel. - 100sf com.mix. - 7sf gel - 8 5/8 wiper plug - 70sf com.mix. Max press. 900#

shut in @ 400#

RECEIVED
STATE CORPORATION COMMISSION

Allied cement co. Elev. 2051' GL.

1-7-85

Remarks: _____
(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

CONSERVATION DIVISION
Wichita, Kansas

DATE 1-16-85

Signed Carl Goodrow (TECHNICIAN)

INV NO. 6521

Jan 4-85