

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-137-20, 313 -00-00
~~NE NE SW~~
SW, Sec. 2, T 5 S, R 22 W E
2310 feet from N/S section line
2310 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5544 ⁸⁹⁰⁸
Operator: TAM OIL & GAS CO.
Name & ~~THORNTON OIL CO.~~
Address 2700 OAK SUITE A
HAYS, KANSAS 67601

Lease Name WALTERS Well # 1
County NORTON
Well Total Depth 3524 feet 114.53
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 7/8 feet 208

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor KELSO CASING PULLING License Number 545
Address CHASE, KANSAS

Company to plug at: Hour: AM Day: 16 Month: 12 Year: 19 83

VERBAL PLUGGING ORDERS GIVEN TO MIKE GOMEZ

(company name) KELSO (phone) _____

were: BOTTOM PLUG - 4SX COM. CEM. ON BOTTOM - SAND TO 3360 - 4SX COM. CEM. ON TOP. - RECOVERED 2022' OF 4 1/2.

TOP PLUG - PUMP DOWN 8 5/8 WITH 3 HULLS - 34 SX. GEL. 100 SX CEM. MIX. 6 SX. GEL. - 8 5/8 PLUG - 70 SX CEM. MIX.

50/50 POZ 60 GEL 3% CC Signed Carl Goodnow
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 9:45 AM Day: 16 Month: 12 Year: 19 83

ACTUAL PLUGGING REPORT AS ABOVE

MAX. 400# SHUT IN 200#
ALLIED.

Remarks: 8908 TAM OIL & GAS CO.

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

RECEIVED
STATE CORPORATION COMMISSION
INVOICED
DATE 12-28-83 DEC 27 1983
INV. NO. 7238-W CONSERVATION DIVISION
Wichita, Kansas

Signed Carl Goodnow
(TECHNICIAN)