

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-147-00915-00-0  
API NUMBER 15-N/A  
LEASE NAME Veeh A  
WELL NUMBER 7

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to  
Cons. Div. Office within  
30 days.

4950 Ft. from S Section Line  
~~310~~  
~~2970~~ Ft. from ~~E~~ Section Line  
SEC. 31 TWP. 5S RGE. 20 (x) or (W)  
COUNTY Phillips  
Date Well Completed 8/21/49  
Plugging Commenced 4/26/95  
Plugging Completed 4/26/95

LEASE OPERATOR OXY USA Inc.

ADDRESS P. O. Box 26100

PHONE# (405) 749-2309 Operators License #5447

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11/10/94 (date)

by Dennis Hamel (KCC District Agent's name).

Is ACO-1 filed? no If not, is well log attached? no

Producing Formation Reagan Depth to Top 3608 Bottom 3618 T.D. 3632

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled Out
Reagan	Oil	3608	3618	8 5/8"	175	
				5 1/2"	3632	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from        feet to        feet each set.

Perf @ 1092-93 & 1792-93. RIH w/ 2 3/8" tbg to 3493' Mixed & pumped 77sks 60/40 pozmix w/10% gel & 1/4#sk Flocele & 200# hulls. Pumped to bottom. Washed pipe /8bbl wtr. Pulled to 2283' & pumped 77sks same mix, displaced w/3bbl wtr. Pulled to 1150' hooked up & circ. good cmt to pit. Pulled rest of tbg. Put on swedge. Top off csg @ 300#, (See back of form)

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Hi-Plains Production Inc. License No. 8003

Address P. O. Box 307, Logan, KS 67646

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: OXY USA Inc.

STATE OF OKLAHOMA COUNTY OF OKLAHOMA, ss.

Jerry Ledlow (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

MAY 07 1995  
05-05-1995

(Signature) [Signature]

(Address) P. O. Box 26100, OKC, OK 73126-0100

SUBSCRIBED AND SWORN TO before me this 2nd day of May, 19 95

[Signature]  
Notary Public

My Commission Expires: 7-14-95

hooked up to 8 5/8"-5 1/2" annulus & pumped 136sks w/100# hulls @ 400#. Shut in & held @ 100#. Cut off csg 5' below ground level.