

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-137-20,361-00-00

LEASE NAME Hazlett

WELL NUMBER 1

SPOT LOCATION 5' E of C NW NE

SEC. 8 TWP. 5S RGE. 22W (# for (W))

COUNTY Norton

Date Well Completed 11/24/85

Plugging Commenced 11/24/85

Plugging Completed 11/25/85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR McGinness Oil Company

ADDRESS 1026 Union Center Building, Wichita, Ks. 67202

PHONE # (316) 267-6065 OPERATORS LICENSE NO. 5255

Character of Well D & A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays, Ks. 67601 - Dale Balthazor

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing formation N/A Depth to top N/A bottom N/A T.D. 3,642'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	241'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

1st Plug @ 3635' w/25 sx cement; 2nd Plug @ 1790' w/25 sx cement;

3rd Plug @ 1040' w/100 sx cement & 1 sx Flocele;

4th Plug @ 270' w/40 sx cement; Bridge Plug @ 40' w/10 sx cement & 2 sx hulls;

15 sx cement in rathole (Plugs calculated by displacement)

60/40 Pozmix, 6% Gel

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Red Tiger Drilling Company License No. 5302
Address 1720 KSB Building, Wichita, Kansas 67202

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

I, Douglas H. McGinness

~~XXXXXXXXXXXXXXXXXXXX~~ (operator) of

(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the above-described well as filed that the same are true and correct, so help me, God.

(Signature) Douglas H. McGinness

(Address) 1026 Union Center Bldg
Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 23 day of Dec, 1985

My Commission expires: April 8, 1989

