

API NUMBER 15-137-20, 174 0001

LEASE NAME Walters

WELL NUMBER #1

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

330' 36³⁰ Ft. from (S) Section Line

330' 19⁸⁰ Ft. from (E) Section Line

LEASE OPERATOR Jerry Patterson, Oil

SEC. 2 TWP. 5S RGE. 22W (E) or (W)

ADDRESS P.O. Box 307, Logan KS 67646

COUNTY Norton

PHONE# (913) 689-4897 OPERATORS LICENSE NO. 9559

Date Well Completed 5/5/80

Character of Well SWD

Plugging Commenced 3/3/0/94

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 3/3/0/94

The plugging proposal was approved on November 10, 1993 (date)

by David P. Williams (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Gorham Sand Depth to Top 3519' Bottom 3520' T.D. 3527'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Gorham Sand	Oil & Water	3519'	3527'	4 1/2	3524'	None
				8 5/8	249'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from ___ feet to ___ feet each set. Rigged up Hi-Plains Production well servicing rig. Talled and run in hole with 2 3/8 tubing. Spot and circulated 50 sacks at 3115'. Pulled up and spot and circulated 50 sacks at 2115'. Pulled up and spot and circulated 80 sacks at 1115'. Included in all was 200 sacks hauls. Spot 20 sacks at top of casing to top off. Plugged with total 200 sacks 60/40 POZ with 10% gel. Hooked up to 8 5/8, could not pump into at 500#'s.

Name of Plugging Contractor Hi-Plains Production Service, Inc. License No. 8003

Address Logan, KS

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Jerry Patterson, Oil

STATE OF Kansas COUNTY OF Phillips, ss.

Jerry Patterson (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.
 (Signature) Jerry Patterson
 (Address) Logan, KS

SUBSCRIBED AND SWORN TO before me this 3rd day of June

Karene K. Triplett
 Notary Public

RECEIVED
 STATE CORPORATION COMMISSION

My Commission Expires: 12/07/96

JUN 07 1994



CONSERVATION DIVISION
 Wichita, Kansas