

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas, 67202

Form CP-4  
Rev. 12-15-80

15-137-20313-00-00

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Norton SEC. 2 TWP. 5S RGE. 22W E/W  
Location as in quarters or footage from lines:  
NE NE SW


Locate Well  
correctly on above  
Section Platt.

Lease Owner Tam Oil & Gas  
Lease Name Walters #1 Well No. \_\_\_\_\_  
Office Address 2700 Oak St. Suite A Hays, Kansas, 67601  
Character of Well (Completed as Oil, Gas or Dry Hole): \_\_\_\_\_  
Date Well Completed \_\_\_\_\_  
Application for plugging filed \_\_\_\_\_  
Plugging commenced 12-12-83  
Plugging completed 12-16-83  
Reason for abandonment of well or producing formation \_\_\_\_\_

\_\_\_\_\_ Depleted  
Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Hays Ks. Office  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom T.D. 3524'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	208'	none
				4-1/2"	3517'	2022'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged off bottom with 4 sacks cement, sand to 3365' and 4 more sacks cement.  
Shot casing @3000', 2700', 2300', 2022' and pulled a total of 50 joints (2022')  
of 4-1/2" casing. Plugged surface with 34 sacks gel mixed with 3 sacks hulls,  
100 sacks cement, 6 sacks gel, released plug and displaced with 70 sacks cement  
50/50 pos, 6% gel, 3% cc.  
Plugging Complete.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.  
R. Darrell Kelso (employee of owner) or (owner or operator) of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso  
Box 347 Chase, Ks. 67524  
(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of December, 19 83

My Commission expires: \_\_\_\_\_  


Irene Hoover  
Notary Public.  
STATE CORPORATION COMMISSION

DEC 22 1983  
12-22-83  
CONSERVATION DIVISION  
Wichita, Kansas