


15-137-00167-00-00

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Norton County, Sec. 4 Twp. 5 Rge. 22W (E) (W)
Location as "NE/CNW/SW" or footage from lines NW NE NW
Lease Owner D. G. Hansen
Lease Name Hemphill Well No. 1
Office Address Logan, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed April 26 19 61
Application for plugging filed April 26 19 61
Application for plugging approved April 26 19 61
Plugging commenced April 26 19 61
Plugging completed April 26 19 61
Reason for abandonment of well or producing formation Too low structurally

If a producing well is abandoned, date of last production _____ 19 ____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3729 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	168.00'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 300'. Set plug. Put in 20 sacks cement. Filled to 165'. Set plug. Put in 20 sacks cement. Filled with heavy mud up to 40'. Set plug. Filled to top with 1 sack hulls and 10 sacks cement.


RECEIVED
STATE CORPORATION COMMISSION
MAY 15 1961
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor C-G Drilling Co. S-15-61
Address 107 Rule Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
G. F. Galloway (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) G. F. Galloway
107 Rule Building
(Address)

SUBSCRIBED AND SWORN to before me this 28th day of April, 19 61
My commission expires May 20, 1963
Vicky Jacobs
Notary Public.



15-137-0067-00-00

WELL LOG

OPERATOR D. G. Hansen SEC. 4-5-22W
 WELL NAME Hemphill #1 LOC. NW NE NW
 TOTAL DEPTH 3729' COUNTY Norton
 COMM. April 18, 1961 COMP. April 26, 1961 STATE Kansas
 RIG NO. 1 ELEVATION 2216 K.B.

CASING: Ran 168.11' (8 jts.) 8-5/8" OD Surface Casing. PRODUCTION: D & A

All measurements taken from the top of rotary bushing.

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0	1550	Shale & Sand		
1550	1827	Red Bed		
1827	1860	Anhydrite		
1860	1950	Shale & Shells		
1950	2255	Shale & Shell		
2255	2350	Shale & Shells		
2350	2480	Shale & Lime	0° - 2500	
2480	2785	Lime & Shale	0° - 2750	
2785	3358	Shale & Lime	0° - 3000	
3358	3450	Lime & Shale	0° - 3250	
3450	3499	Lime	0° - 3500	3457-3490' DST
3499	3729	Lime & Shale		3650-3656' DST

RECEIVED
STATE CORPORATION COMMISSION

MAY 15 1961 5-15-61

CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS }
 COUNTY OF SEDGWICK } SS.

The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.
 By G. F. Galloway
 G. F. Galloway

SUBSCRIBED AND SWORN TO, BEFORE ME, THIS 28th day of April, 1961.
 My commission expires: May 20, 1963
Vicky Jacobs
 Vicky Jacobs - Notary public

