

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
P. O. BOX 17027
Wichita, Kansas 67217

Rev. 3-15-72
FORM CP-1

RECEIVED
STATE CORPORATION COMMISSION

JAN 30 1974

CONSERVATION DIVISION
Wichita, Kansas

1-30-74

WELL PLUGGING APPLICATION FORM
File One Copy

15-137-20090-00-00

Lease Owner Abercrombie Drilling, Inc.
Address 801 Union Center, Wichita, Kansas 67202
Lease (Farm Name) HILDEBRAND Well No. 1
Well Location SE SW SW Sec. 15 Twp. 5S Rge. (E) 23 (W)
County Norton Total Depth 3600' Field Name
Oil Well Gas Well Input Well SWD Well Rotary D & A X
Well Log filed with application as required Yes
Date and hour plugging is desired to begin 7:00 a.m. 1-26-74

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

Name of company representative authorized to be in charge of plugging operations:

Joe Weber Address Great Bend, Kansas 67530

Plugging Contractor Abercrombie Drilling, Inc. License No.

Address 801 Union Center, Wichita, Kansas 67202

Invoice covering assessment for plugging this well should be sent to:

Name Abercrombie Drilling, Inc.

Address 801 Union Center, Wichita, Kansas 67202

and payment will be guaranteed by applicant or acting agent.

Signed: Jerry A. Langrehr
Applicant or Acting Agent
Jerry A. Langrehr, V.P.
Date: January 28, 1974

15-137-20090-00-00

CONTRACTOR'S WELL LOG

OPERATOR:	Abercrombie Drilling, Inc.
CONTRACTOR:	Abercrombie Drilling, Inc.
WELL NAME:	HILDEBRAND #1
LOCATION:	SE SW SW Sec. 15-5S-23W Norton County, Kansas
GEOLOGIST:	Jack K. Wharton
SPUD DATE:	January 20, 1974
COMPLETION DATE:	January 26, 1974

0	240	Sand, Clay and Shale
240	1130	Shale
1130	1230	Sand
1230	1470	Shale
1470	1590	Sand
1590	1842	Shale
1842	1873	Anhydrite
1873	2459	Shale
2459	3414	Lime and Shale
3414	3600	Lime
	3600	Rotary Total Depth

Drilled 240' of 9-7/8" surface hole. Set 7-5/8" surface casing at 238' w/140 sx. cement, 3% ca.cl. Cement circulated. Plug down at 3:45 p.m. 1-20-74.
Dry and Abandoned

ELECTRIC LOG TOPS

Anhydrite	1844 (+ 363)
B/Anhydrite	1875 (+ 332)
Heebner	3356 (-1149)
Toronto	3388 (-1181)
Lansing	3400 (-1193)
Base/Kansas City	3587 (-1380)
ELTD	3601 (-1394)

ELEVATION STATE CORPORATION COMMISSION
 2207 K.V.
 2205 D.F.
 2199 C.J.
 RECEIVED
 JAN 30 1974
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

1-30-74

Jerry A. Langrehr, Vice President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the HILDEBRAND #1, SE SW SW Section 15-5S-23W, Norton County, Kansas.

ABERCROMBIE DRILLING, INC
 By: Jerry A. Langrehr
 Jerry A. Langrehr
 Vice President

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 28th day of January, 1974.

Beverly Mann
 Beverly Mann, Notary Public

My Commission Expires:
 February 10, 1975

State of Kansas



15-137-20090-00-06

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

January 30, 1974

WELL PLUGGING AUTHORITY

Well No.	1
Lease	Hildebrand
Description	C SE SW SW 15-5-23W
County	Norton
Total Depth	3600'
Plugging Contractor	Abercrombie Drilling


Abercrombie Drilling, Inc.
801 Union Center
Wichita, Kansas 67202

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after 90 days from the above date.

Yours very truly,


J. Lewis Brock, Administrator

Mr. W. L. Nichols, P. O. Box 157, Morland, Kansas 67650
is hereby assigned to supervise the plugging of the above named well.