

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
800 BITTING BUILDING  
WICHITA, KANSAS

15-137-00059-00-00

WELL PLUGGING APPLICATION FORM

Lease Owner Harry Gore Address 400 Brown Bldg.,  
(Applicant) Wichita, Kansas.  
Lease (Farm Name) Leidig Well No. #1  
Well Location NE-NE-NE Sec. <sup>15</sup>~~5~~ Twp. <sup>5</sup>~~15~~ Rge. 23 (E)-(W) W  
County Norton Field Name (if any) Wildcat  
Total Depth 3752' Oil      Gas      Dry Hole Dry Hole  
Was well log filed with application? Yes. If not, explain: \_\_\_\_\_

Date and hour plugging is desired to begin 8-16-51 2:A.M.

Plugging of the well will be done in accordance with the Rules and Regulations of the State Corporation Commission, or with the approval of the following exceptions: Explain fully any exceptions desired.

(Use an additional sheet if necessary) \_\_\_\_\_

Name of the person on the lease in charge of well for owner \_\_\_\_\_

T.C. Strain Address Box 188, Hays, Kansas.

Name of Plugging Contractor Strain Drilling Company

Address Box 188 Hays, Kansas.

Invoice covering assessment for plugging this well should be sent to

Harry Gore Address 400 Brown Bldg. Wichita, Ks.

and payment will be guaranteed by applicant.

*T.C. Strain*  
T.C. Strain

RECEIVED

STATE CORPORATION COMMISSION

PLUGGING  
FILED SEC 15 T 5 R 23W  
BOOK PAGE 104

AUG 21 1951

CONSERVATION DIVISION  
Wichita, Kansas

August 18, 1951

Applicant or Acting Agent

Date

8-16-51

8-21-51

WELL LOG

15-5-23W

COMPANY: Harry Gore

LEASE: Letdig #1

NE-NE-NE-, Sec 15,  
Twp. 15, Rge. 23W,  
Norton County, Ka.

ELEVATION: 2187 Derrick Floor

NOTE: All meas. rotary bushings.

0	219 Soil & shale
219	585 Shale
585	1250 Shale
1250	1395 Shale
1395	1430 Shale & sand
1430	1575 Sand
1575	1595 Shale
1595	1600 Shale
1600	1995 Shale & redbed
1895	1800 Anhydrite
1800	1900 Shale
1900	2140 Shale & shells
2140	2245 Shale
2245	2315 Shale
2315	2340 Shale
2340	2375 Lime & shale
2375	2470 Shale
2470	2620 Lime & shale
2620	2715 Lime & shale
2715	2850 Lime
2800	2840 Lime & shale
2840	2910 Lime
2910	3020 Shale & lime
3020	3100 Lime & shale
3100	3140 Lime & shale
3140	3205 Lime & shale
3205	3305 Lime
3305	3370 Lime
3370	3375 Lime
3375	3390 Lime
3390	3425 Lime
3425	3440 Chert & lime
3440	3495 Lime
3495	3495 Lime
3495	3540 Lime
3540	3545 Lime
3545	3555 Lime
3555	3568 Lime
3568	3615 shale
3615	3650 Shale
3630	3685 Shale
3685	3695 Shale
3695	3735 Arbuckle
3735	3745 Arbuckle
3745	3752 Arbuckle

COMMENCED: 8-1-51  
COMPLETED: 8-15-51

CASING RECORD:

5 5/8" Surface casing set at 219'  
w/175 sacks cement, 2 sks CG,  
by Globe Cementing Co.

D.S.F. Johnston Testing Co.

3361-3372' Tool open 1 hour. Rec-  
covered 65 feet muddy salt water.  
B.H.P. 15 min. 1130#

3393-3427' Tool open 1 hour. Rec-  
covered 390 feet mud with trace of salt  
water. B.H.P. 15 min. 1200#

3438-3491' Tool open 1/2 hour.  
Recovered 30 feet mud. B.H.P.  
15 min. 0.

3501-3549' Tool open 1/2 hour.  
Recovered 30 feet mud. B.H.P.  
15 min. 0.

Run Schlumberger log to Total Depth.

3752 T.D. (D.S.)

TOPS: Rig Floor Meas.

Anhydrite	1625
Topeka	3158
Heebner	3338
Lansing (K.C.)	3380

RECEIVED  
STATE OF KANSAS

AUG 20 1951

Conservation Commission	Miss K.C.	3568
Wichita Falls	Arbuckle	3735-3752-1500
	Total Depth	3752

STATE OF KANSAS )  
COUNTY OF ELLIS )

I hereby affirm that the above and foregoing is a true and correct copy of the log of the Letdig #1, located NE-NE-NE, Sec. 15, Twp. 15, Rge. 23W, Norton County, Kansas.

CONTRACTOR: Strain Drilling Co.

By J.C. Strain  
T.C. Strain

Subscribed and sworn to before me this 18 day of August, 1951

My Commission expires July 18, 1955

PLUGGING

FILE NO. 15-5-23W  
BOOK PAGE 104 LINE 7  
NOTARY PUBLIC



15-137-00099-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
800 BITTING BUILDING  
WICHITA, KANSAS

August 17, 1951

Well No. 1  
Lease Laidig  
Description NE NE NE Sec. 15-5-23W  
County Norton  
File No. 104-7

Mr. Harry Gore,  
400 Brown Bldg.,  
Wichita, Kansas

Dear Sir:

This letter is your authority to plug the above subject well, in accordance with the Rules and Regulations of the State Corporation Commission. When you are ready to plug this well, please contact our District Plugging Supervisor, Mr. Eldon Petty, Box 326, Hays, Kansas.

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION

BY:

*J. P. Roberts*  
J. P. ROBERTS

cc: DISTRICT PLUGGING SUPERVISOR