

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. MARKET, ROOM 2078
WICHITA, KS 67202

WELL PLUGGING RECORD
K.A.R. 82-3-117

API NUMBER 15-137-20,125 -00-00

LEASE NAME Archer-Nelson

WELL NUMBER 4

990 Ft. from S Section Line

4290 Ft. from E Section Line

SEC 12 TWP 5S RGE 22 W

COUNTY Norton

Date Well Completed 3/21/78

Plugging Commenced 7/31/02

Plugging Completed 8/1/02

RECEIVED
AUG 22 2002
8-22-2002
KCC WICHITA

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Daystar Petroleum, Inc.

ADDRESS 1321 W. 93rd N., Valley Center, KS 67174

PHONE # 316-755-3523

Character of Well oil

(Oil, Gas, D & A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 7/31/02 (date)

by KCC, District #4, Richard Williams; verbal (KCC District Agent's Name)

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation LKC; Regan Depth to Top 3300 Bottom 3520 T.D. 3520

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
LKC	oil & water	0	288	8 5/8"	288	0
Regan	oil & water	0	3519	4 1/2"	3519	0

Describe in detail the manner in which the well was plugged, indicating where the mud was fluid placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Mixed 50 sx 60/40 poz w/ 10% gel & 2 sx hulls; spotted from approx 3330' to 3430' w/ 2" tbq.

Pull tbq to 2450'; mixed and pumped 100 sx same cement. Circ to surface.

Pulled tbq. Pump 20 sx on top. Mixed 50 sx cement w/ 100# hulls; Pressured to 700#; Shut in.

Name of Plugging Contractor Plains Inc. License No. 4072

Address P.O. Box 346; Ness City, Ks 67560-0346

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Daystar Petroleum, Inc.

STATE OF KANSAS COUNTY OF Sedgwick, ss.

Charles Schmidt (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Charles Schmidt

(Address) 1321 W. 93rd N., Valley Center, KS 67174

SUBSCRIBED AND SWORN TO before me this 21st day of August 2002

Marsha Breitenstein
Notary Public

My commission Expires: September 15, 2003



OK

ALLIED CEMENTING CO., INC. 12029

Federal Tax I.D.# [REDACTED]

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT: Oakley

DATE <u>8-1-02</u>	SEC. <u>12</u>	TWP. <u>5</u>	RANGE <u>22^W</u>	CALLED OUT	ON LOCATION <u>9:45 AM</u>	JOB START	JOB FINISH
LEASE <u>Archer Nelson</u>	WELL # <u>4</u>	LOCATION <u>Deansmore 1S-31421-10N</u>		COUNTY <u>Norton</u>		STATE <u>Kan</u>	
<input checked="" type="radio"/> OLD OR NEW (Circle one)							

CONTRACTOR Playas Well Service

TYPE OF JOB CHP

HOLE SIZE _____ T.D. _____

CASING SIZE 4 1/2 DEPTH _____

TUBING SIZE _____ DEPTH _____

DRILL PIPE _____ DEPTH _____

TOOL _____ DEPTH _____

PRES. MAX _____ MINIMUM _____

MEAS. LINE _____ SHOE JOINT _____

CEMENT LEFT IN CSG. _____

PERFS. _____

DISPLACEMENT _____

OWNER Same

CEMENT

AMOUNT ORDERED 275 sks 60/40 per

10% let, 500# Hulls

(used 220 sks)

COMMON	<u>132 sks</u>	@	<u>6.65</u>	<u>877.80</u>
POZMIX	<u>88 sks</u>	@	<u>3.55</u>	<u>312.40</u>
GEL	<u>19 sks</u>	@	<u>10.00</u>	<u>190.00</u>
CHLORIDE		@		
<u>Hulls</u>	<u>5 sks</u>	@	<u>18.00</u>	<u>90.00</u>
		@		
		@		
		@		
		@		
HANDLING	<u>299 sks</u>	@	<u>1.10</u>	<u>328.90</u>
MILEAGE	<u>4¢ per sk/mile</u>			<u>992.88</u>

EQUIPMENT

PUMP TRUCK CEMENTER Walt

300 HELPER Wayne

BULK TRUCK DRIVER Fuzzy

361 DRIVER _____

BULK TRUCK DRIVER _____

RECEIVED

AUG 22 2002

TOTAL 2,791.78

KCC WICHITA SERVICE

REMARKS:

Mixed 50 sks cement w/ 2-Hulls
down 2" Tubing to 3430
Pull Tubing to 2450 mixed 100
sk's cement w/ 2-Hulls, Circ cement
to surface, Pull Tubing, Put 20 sks
on Top,
Mixed 50 sks cement w/ 100# Hulls
Pressure to 700#, Shut in

DEPTH OF JOB _____

PUMP TRUCK CHARGE _____ 475.00

EXTRA FOOTAGE _____ @ _____

MILEAGE 83 miles @ 3.00 249.00

PLUG _____ @ _____

_____ @ _____

_____ @ _____

TOTAL 724.00

CHARGE TO: Daystar

STREET _____

CITY _____ STATE _____ ZIP _____

FLOAT EQUIPMENT

_____ @ _____

_____ @ _____

_____ @ _____

_____ @ _____

_____ @ _____

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TOTAL _____

TAX _____

TOTAL CHARGE _____

DISCOUNT _____ IF PAID IN 30 DAYS

SIGNATURE [Signature]

PRINTED NAME _____