

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-177

API NUMBER 15-137-20,091 -00-00

LEASE NAME Stenger A

WELL NUMBER 2

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

2970 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 11 TWP. 5S RGE. 22W (E)or(W)

COUNTY Norton

Date Well Completed 2/27/74

Plugging Commenced 05/03/95

Plugging Completed 05/03/95

LEASE OPERATOR R.P. Nixon Oper. Inc.

ADDRESS 207 West 12th Hays, KS 67601

PHONE #(913) 628-3834 OPERATORS LICENSE NO. 5252

Character of Well oil

(Oil, Gas, D&A, SWD. Input, Water Supply Well)

The plugging proposal was approved on 05/03/95 (date)

by Carl Goodrow (KCC District Agent's Name).

Is ACO-1 Filed? yes If not, is well log attached? \_\_\_\_\_

Producing Formation L/KC & Reagan Depth to Top 3244' Bottom 3500' T.D. 3500'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS, OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 7/8"	276'	None
				4 1/2"	3499'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.  
Perfed 4 1/2" casing with 2 holes @ 990' and 2 holes @ 1740'. Pumped down 4 1/2" casing w/25 sx 60/40 Poz, 10% gel and 200# hulls & 7 gel; then pumped 150 sx same cement w/300# hulls. Pressured up to 1200# and shut-in press. was 500#. Pumped down casing annulus w/10 sx same cement and pressured to 500#.

(If additional description is necessary, use BACK of this form.)


Name of Plugging Contractor Jay-Lan Corp. License No. 5128

Address 207 West 12th Hays, KS 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: R.P. Nixon Operations, Inc.

STATE OF Kansas COUNTY OF Ellis, ss.

Dan Nixon, president, R.P. Nixon Oper. Inc. (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.



(Signature) [Signature] **MAY 25 1995**  
(Address) 207 West 12th Hays, KS 67601

SUBSCRIBED AND SWORN TO before me this 24th day of May, 1995

Jolene H. Klaus  
Notary Public

My Commission Expires: 2-5-98