


15-137-00227-00-00

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Norton County. Sec. 9 Twp. 5S Rge. 22 (E) W (W)
Location as "NE/CNW $\frac{1}{2}$ SW $\frac{1}{2}$ " or footage from lines C SE SW NW
Lease Owner Cities Service Oil Company
Lease Name Thompson "D" Well No. 1
Office Address Bartlesville, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed August 27 19 59
Application for plugging filed August 27 19 59
Application for plugging approved August 27 19 59
Plugging commenced August 27 19 59
Plugging completed August 27 19 59
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Al Fabricius, Hill City
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3634 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	241'	8-5/8"	241'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

From 3634' to 600' - heavy rotary mud
600' to 538' - plug, 1/2 sk hulls, 20 sacks cement
538' to 230' - heavy rotary mud
230' to 168' - plug, 1/2 sk hulls, 20 sacks cement
168' to 40' - heavy rotary mud
40' to 6' - plug, 1/2 sk hulls, 10 sacks cement
6' to surface - cellar
rathole - 1 sack cement

RECEIVED
STATE CORPORATION COMMISSION

SEP 17 1959

CONSERVATION DIVISION
Wichita, Kansas

9-17-59

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Peel Brothers, Inc.
Address P. O. Box 359, Hoisington, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
Cities Service Oil Company, M. M. Hardin (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) M. M. Hardin

P. O. Box 553, Russell, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of September, 1959

My commission expires March 17, 1963

W. J. Smith
Notary Public.

PLUGGING

File Sec. 9 T. 5 R. 22W

Book Page 2 Line 29