

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

Docket # CD-9785

API NUMBER 15-137-20,057-
LEASE NAME Stanger A
WELL NUMBER 3-SWD
990 Ft. from ③ Section Line
2310 Ft. from ② Section Line
SEC. 11 TWP. 5 RGE. 22W(E) or (W)

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Double Eagle Exploration Inc.
ADDRESS 800 West 47th Street Suite 318 KS. MO 64112 COUNTY Norton
PHONE# (816) 531-3516 OPERATORS LICENSE NO. 6009
Character of Well SWD
(Oil, Gas, D&A, SWD, Input, Water Supply Well)
The plugging proposal was approved on 8-15-97 (date)
by _____ (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____
Producing Formation Cedar Hill Depth to Top 1000' Bottom 1300' T.D. 1350'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS			CASING RECORD			
Formation	Content	From	To	Size	Put In	Pulled out
<u>Cedar Hill</u>		<u>1000</u>	<u>1350</u>	<u>4 1/2"</u>		<u>MANP</u>


Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each set.
2 3/4" tubing to 1420 Spot 35 Sacks Cement w/ 100# Hull - Tubing stuck Shot off at 700 ft
Circs Cement to surface w/ 55 Sacks Cement Pulled Tubing 4 1/2" Surge in 85 Sacks
1000# MAX. PSI Shot in at 500# Could Not Pump in to Back Side Full of Cement
to top

Name of Plugging Contractor Allied Cementing Co. Inc License No. _____
Address P.O. Box 31 Russell KS. 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Double Eagle Exploration Inc
STATE OF KS COUNTY OF Norton, ss.

Rat Walters (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Rat Walters
(Address) Wesley, KS



SUBSCRIBED AND SWORN TO before me this 17th day of November, 19 97
Erin J. Shauers, Notary Public
My Commission Expires: 10/3/98