

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: PETEX, INC.
Address: 4175 S. FARM RD 193, ROGERSVILLE, MO 65742
Phone: (417) 887-1225 Operator License #: 8541
Type of Well: OIL Docket #: _____
(Oil, Gas, D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 12-07-04 (Date)
by: HERB DEINES (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
MORROW Depth to Top: 5005 Bottom: 5008' T.D. 5198'
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-199-20244-0000
Lease Name: WEIS
Well Number: 1
Spot Location (QQQQ): _____ - SW - SW - NW
2970 Feet from North / South Section Line
4970 Feet from East / West Section Line
Sec. 20 Twp. 15 S. R. 41 East West
County: WALLACE
Date Well Completed: 1-31-97 1-16-1999 *KCC BE m 12/22/04 RBDMS*
Plugging Commenced: 12-8-04
Plugging Completed: 12-13-04

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
MORROW	OIL	0'	5194'	5-1/2"	5194'	0'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs are used, state the character of same, depth placed from (bottom), to (top) for each plug set.

2-7/8" TBG STUCK IN CSG. PUMPED DOWN TBG W/ 40 SX CMT, DISPLACED W/ 26 BBL WTR, SHOT OFF TBG @ 4500'.
PULLED TBG TO 4470' & PUMPED 29 SX GEL, 40 SX CMT & 50# HULLS. TOH W/ TBG. PUMPED DOWN CSG W/ 150 SX,
MAX PRESS 600#, SICP 0#. PUMPED DOWN 8-5/8"x 5-1/2" ANNULUS W/ 5 SX CMT, MAX PRESS 200#.
PLUGGING COMPLETE @ 3:30 PM, 12-13-04. USED 235 SX 60-40 POZ W/ 10% GEL, 50# HULLS & 29 SX GEL

Name of Plugging Contractor: ALLIED CEMENTING CO, INC. License #: 99996
Address: P.O. BOX 31, RUSSELL, KS 67665-0031
Name of Party Responsible for Plugging Fees: PETEX, INC.
State of KANSAS County, BARTON, ss.

RECEIVED
DEC 21 2004
KCC WICHITA

CONSULTING ENGINEER (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Thomas Larson LARSON ENGINEERING, INC.
(Address) 562 WEST HIGHWAY 4 OLMITZ, KS 67564-8561

DEBRA J. LUDWIG
Notary Public - State of Kansas
My Appt. Expires 5/5/2008

SUBSCRIBED and SWORN TO before me this 20th day of December, 2004
Debra J Ludwig My Commission Expires: 5/5/2008
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Bu