

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117**

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: R.J.M. Oil Company
 Address: P.O. Box 256
 Phone: (620) 587-3910 Operator License #: 30458
 Type of Well: oil Docket #: _____
 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
 The plugging proposal was approved on: November 10th, 2004 (Date)
 by: Virgil Clothier (KCC District Agent's Name)
 Is ACO-1 filed? Yes No If not, is well log attached? Yes No
 Producing Formation(s): List All (If needed attach another sheet)
 _____ Depth to Top: 3261' Bottom: N/A T.D. 3272'
 _____ Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-NAD53-01131-00-00
 Lease Name: Phillips
 Well Number: #2
 Spot Location (QQQQ): SE - SE - SW -
330 Feet from North / South Section Line
2970 Feet from East / West Section Line
 Sec. 34 Twp. 16 S. R. 10 East West
 County: Ellsworth
 Date Well Completed: 6/27/44
 Plugging Commenced: 12/13/04
 Plugging Completed: 12/16/04

*KCC
from
12/26/04
RBDMS*

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	Surface	0'	362'	8-5/8"	362'	0'
	Production	0'	3261'	5-1/2"	3261'	0'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Bakhoie dug out lead line, capped and backfilled. M.I.R.U. Trip out of hole with polish rod, liner, 2 - 4' subs, 6' sub, 6-(7/8") rods, 112-(3/4") rods & 4' MPX valve. Riggged over and trip out of hole with tubing-to fluid. Riggged up swab equipment. Trip out of hole with rest of tubing (99 joints), barrel and 15' mud anchor. Sanded well off to 3200'. Decided not to recover pipe. Called state for orders. Lined up perforators and cementers. M.I.R.U. Log-Tech. Set cast iron bridge plug at 3050'. Perforated at 1300', 1000' and 412' (2 holes per shot). Trip in hole with 1300' of tubing. Pumped 35 sx at 1300'. Pulled to 1000'-broke circulation. Pumped 35 sx-pulled to 400'-pumped 80 sx to circulate cement to surface. Washed up and pulled rest of tubing. Top well off-R.D.M.O.

Name of Plugging Contractor: D.S. & W. Well Servicing, Inc License #: 6901
 Address: P.O. Box 231, Claflin, Kansas 67525
 Name of Party Responsible for Plugging Fees: R.J.M. Oil Company

**RECEIVED
DEC 23 2004**

State of Kansas County, Barton, ss.
Edward S. Nemnich (Employee of Operator) or (Operator) on above described well is personally

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

KAREN J. MITCHELL
 Notary Public - State of Kansas
 My Appt. Expires 4/13/06

Edward S. Nemnich
 (Signature)

P.O. Box 231, Claflin, Kansas 67525
 (Address)

SUBSCRIBED and SWORN TO before me this 22nd day of December, 20 04

Karen J. Mitchell
 Notary Public

My Commission Expires: 4/13/06

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Bw