

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Baird Oil Company LLC  
Address: PO Box 428 Logan, Ks 67646  
Phone: (785) 689-7456 Operator License #: 32819  
Type of Well: oil Docket #: \_\_\_\_\_  
*(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)*  
The plugging proposal was approved on: 8/19/2004 (Date)  
by: Herb Deines (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (if needed attach another sheet)  
Kansas City Depth to Top: 3449 Bottom: 3636 T.D. 3715  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-065-22,491-00-00  
Lease Name: Boys  
Well Number: #2  
Spot Location (QQQQ): NW - SW - NW -  
3630 Feet from  North /  South Section Line  
4950 Feet from  East /  West Section Line  
Sec. 8 Twp. 6 S. R. 21  East  West  
County: Graham  
Date Well Completed: 11/03/1988  
Plugging Commenced: 12/09/2004  
Plugging Completed: 12/09/2004

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Topeka	water	3202	3406	8 5/8	227	none
Kansas City	oil and water	3449	3636	5 1/2	3695	none

RECEIVED  
DEC 22 2004  
KCC WICHITA

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Pressured up 8 5/8 to 500# and it held. Hooked up to 5 1/2 casing and started plugging with 200# of hulls and 33 sacks of cement. Pumped a 41 sack gel spacer. Started cement with 300# of hulls and 97 sacks of cement. Casing loaded and pumped 130 sacks of Multi-Density Cement.


Name of Plugging Contractor: Swift Services, Inc. License #: \_\_\_\_\_  
Address: PO Box 466 Ness City, Ks 67560  
Name of Party Responsible for Plugging Fees: Baird Oil Company LLC PO Box 428 Logan, Ks 67646  
State of Kansas County, Phillips, ss.

Jim R. Baird (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]  
(Address) PO Box 428 Logan, Ks 67646

SUBSCRIBED and SWORN TO before me this 17 day of December, 20 04

Robert B. Hartman My Commission Expires: 3/29/2007  
Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

[Signature]

JOB LOG

SWIFT Services, Inc.

DATE 12-09-04 PAGE NO. 7

CUSTOMER Sand Oil WELL NO. #2 LEASE Boys JOB TYPE P7A TICKET NO. 7450

Table with columns: CHART NO., TIME, RATE (BPM), VOLUME (BBL/GAL), PUMPS (T, C), PRESSURE (PSI) (TUBING, CASING), and DESCRIPTION OF OPERATION AND MATERIALS. Includes handwritten entries for operations like 'ON Location, Sit up, Discuss Job w/ Station man' and 'Start CMT w/ Halls 200\* 33SKS'.

RECEIVED DEC 22 2004 KCC WICHITA

Thank You! DAVE, Blaine, Brett

**JOB LOG**

**SWIFT Services, Inc.**

DATE 12-09-04 PAGE NO. 2

CUSTOMER Baird Oil WELL NO. B-10WWD LEASE Boys JOB TYPE PTA TICKET NO. 7460

CHART NO.	TIME	RATE (BPM)	VOLUME (BBL)(GAL)	PUMPS		PRESSURE (PSI)		DESCRIPTION OF OPERATION AND MATERIALS
				T	C	TUBING	CASING	
	1040							ON Location, Setup Trucks, 8 3/8 273' 5 1/2 14" TO 3615 p 3388-3607
	1050		2		✓		475	Hook up to 8 3/8 Holds Release PSI
								Hook up to 5 1/2 csg
	1100	4	0		✓		50	Start CMT w/ 200# Huls 33SKS
		4	18		✓		50	
		4	18		✓		50	Start Gel Spacer
		4	67		✓		475	Loaded
		4	77		✓		400	Start CMT w/ 300# Huls 97 105SKS
	1121	0	78		✓		300	Pickup Rock out of Water Truck Get Rock out of Pump
	1126	3.5	78		✓		400	Start CMT w/ Huls
		3.5	90		✓		600	
		3.5	100		✓		700	
		3.5	117		✓		800	
	1138	3.5			✓		600	Pump Missing out
		3.0	118		✓		800	get picked up 130SKS SMD
	1142	3.0	129		✓		800	
	1143		129		✓		550	ZSP
	1148		129		✓		475	Smu
							475	Close in, Release
	1200							WASH UP
	1220							Reckup
	1245							pick up Iron off 1st well
	1250							Trucks
	1330							pick up Iron off 2nd well
	1345							Job Complete
								Thank You! Dave, Blaine, Brett

RECEIVED  
DEC 22 2004  
KCC WICHITA

BAIRD OIL COMPANY LLC  
OIL AND GAS PRODUCTION  
P.O. BOX 428  
LOGAN, KANSAS 67646  
PHONE 785-689-7456

JIM R. BAIRD, PRESIDENT  
ROBERT B. HARTMAN, EXEC. VICE - PRESIDENT  
LELAND R. BAIRD, VICE PRESIDENT  
STACI L. HARTMAN, SEC./TREAS.

JAS. W. BAIRD (DECEASED)

RECEIVED  
DEC 22 2004  
KCC WICHITA

12/20/2004


KCC-Conservation Division  
130 S. Market-Room 2078  
Wichita, Ks 67202

Re: CP-4 Forms

Dear Folks,

Enclosed please find two CP-4 Forms on the Boys #2 and the Boys B-1 OWWO. I have also enclosed a copy of the cement tickets.

Sincerely,

  
Jim R. Baird