

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
P. O. BOX 17027
Wichita, Kansas 67217

Rev. 3-15-72
FORM CP-1
RECEIVED
STATE CORPORATION COMMISSION
NOV 27 1973
CONSERVATION DIVISION
Wichita, Kansas
11-27-73

WELL PLUGGING APPLICATION FORM
File One Copy

Lease Owner Dane G. Hansen Trust 15-137-00031-00-00
Address Logan, Kansas 67646
Lease (Farm Name) Hansen 'D' Well No. 1
Well Location SW NW Sec. 26 Twp. 5S Rge. 21 (E) (W) X
County Norton PB Total Depth 3440 3720 Field Name West Ray
Oil Well X Gas Well Input Well SWD Well Rotary D & A
Well Log filed with application as required Yes
Date and hour plugging is desired to begin Before January 1, 1974

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

Name of company representative authorized to be in charge of plugging operations:

Harold Parsons Address Logan, Kansas

Plugging Contractor Southwest Casing Pulling Company License No. 399

Address Box 364, Great Bend, Kansas

Invoice covering assessment for plugging this well should be sent to:

Name Dane G. Hansen Trust

Address Logan, Kansas 67646

and payment will be guaranteed by applicant or acting agent.

Dane G. Hansen Trust
Signed: By: Dotty Jane Bittel
Applicant or Acting Agent

Date: November 26, 1973

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bldg., Wichita, Kansas


Company - CITIES SERVICE & HELMERICH & PAYNE
Farm - Hansen "D" No. 1

SEC. 26 T. 5 R. 21 W
C SW NW
660' N 660' E of W/4 Corner

DISCOVERY WELL

Total Depth. 3720 Rot. = 3717 SLM
Comm. 3-7-45 Comp. 3-20-45
Shot or Treated.
Contractor. Helmerich & Payne, Inc.
Issued. 7-21-45

County. Norton
KANSAS



CASING:
10 3/4" 148' Cem.
5 1/2" 3717' Cem.

Elevation. _____

Production. Phy. Pot. 102 BO,
5% wtr in 24 hrs.

Figures indicate Bottom of Formations.

sand	0-60	8 shots 3646-53'; 100' mud & wtr. & show oil in 15 mins.
gravel sdy	90	
sand & gravel	140	11 shots 3650-54'; 150' fluid in 45 mins., 2308' fluid (mud, oil & wtr) in 2 1/4 hrs.
shale	190	
shale & sand	280	
shale & shells	600	11 shots 3650-54'; 2800' fluid in 3 hrs.
sand	800	
shale & shells	1050	
sand	1120	Set retainer @ 3611' & squeezed w/128 sacks cement; 118 sacks through perforations @ 1000 # to 3000 # pressure.
shale & sand	1460	
sand	1550	
red bed & shale	1600	
shale & shells	1810	
anhydrite	1875	Drilled cement to 3697 SLM
shale & shells	2350	
lime	2390	Perf. 12 shots 3650-54'; 1/2 B fluid, good show oil, in 15 mins.
shale & shells	2450	
shale sdy	2500	
shale & shells	2540	12 shots 3650-54'
shale sdy	2550	12 shots 3654-56'; 100' fluid in 30 mins., 500' fluid (mostly oil) in 1 1/2 hrs., 1200' fluid (135' wtr & 1065' oil) in 12 hrs.
shale & shells	2610	
shale sdy	2640	
shale & shells	2714	
shale sdy	2728	Water exhausted.
lime	2762	Swbd 5 bbls oil per hr. through tbg.
shale & shells	2920	
lime & shale	2965	
shale & lime	3005	
shale sdy	3020	
lime & shale	3212	
lime	3242	
lime cherty	3260	
lime & shale	3333	
lime	3471	
lime sdy	3476	
lime	3487	
lime sft	3492	
lime	3558	
lime sft	3571	
lime	3585	
lime & shale	3620	
cored sand & lime (rec. 10')	3630	
shale & shells	3663	
lime	3720	

3720 Rot. T.D. = 3717 SLM
Total Depth.

Ran Schlumberger

Tops:
K. C. 3338
Guthrie 3612
Lorr. Arbuckle 3660
Perforation 67'
Drilled cement to 3697' SLM

RECEIVED
STATE CORPORATION COMMISSION
NOV 27 1973
CONSERVATION DIVISION
Wichita, Kansas

State of Kansas



15-137-00081-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

November 27, 1973

WELL PLUGGING AUTHORITY

Well No.	1
Lease	Hansen "D"
Description	C SW NW 26-5-21W
County	Norton
Total Depth	3720'
Plugging Contractor	Southwest Casing Pulling Co.


Dane G. Hansen Trust
Logan, Kansas 67646

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after 90 days from the above date.

Yours very truly,


J. Lewis Brock, Administrator

Mr. ~~W. E. Nichols, Box 157, Morland, Kansas 67650~~
is hereby assigned to supervise the plugging of the above
named well.