

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 2/89

RECEIVED
STATE CORPORATION COMMISSION
FEB 05 1992
CONSERVATION DIVISION
WICHITA, KANSAS
2-5-92

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-137-20,108 -00-00 (of this well).

(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR R.P. Nixon Oper. Inc. OPERATOR'S LICENSE NO. 5252 *6-92*

ADDRESS 207 W. 12th Hays, KS 67601 PHONE # (913)628-3834

LEASE (FARM) Nelson C WELL NO. 1 WELL LOCATION SE NE SW COUNTY Norton

SEC. 12 TWP. 5S RGE. 22W (E) or (W) TOTAL DEPTH 3493' PLUG BACK TD open hole

Check One:

OIL WELL GAS WELL D & A SWD or INJ WELL DOCKET NO. _____

SURFACE CASING SIZE 8 5/8" SET AT 236' CEMENTED WITH 165 SACKS

CASING SIZE 4 1/2" SET AT 3488' CEMENTED WITH 100 SACKS

PERFORATED AT L/KC - 3376'-78' 3387'-89' 3406'-08' Reagan Sand - Open hole

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING hole @ approx. 3042'

According to KCC rules & regulations

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? IS ACO-1 FILED? drilled before it was required
(If not explain.)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 10 am 2-4-92

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Paul Nixon PHONE # (913) 628-3834

ADDRESS 207 West 12th Hays, KS 67601

PLUGGING CONTRACTOR Jay-Lan Corp. LICENSE NO. 5128 *6-92*

ADDRESS 207 West 12th Hays, KS 67601 PHONE # (913) 628-1316

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: *Paul Nixon*
(Operator or Agent)

DATE: 2-3-92

(4)

CONTRACTOR'S WELL LOG

NELSON C#1
15-137-20108-00-00

OPERATOR: R. P. Nixon
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: NELSON #3
 LOCATION: SE NE SW Section 12-5S-22W
 Norton County, Kansas
 SPUD DATE: March 3, 1976
 COMPLETION DATE: March 9, 1976

0	246	Clay, sand & shale
246	1089	Sand & shale
1089	1666	Shale & sand
1666	1696	Anhydrite
1696	3045	Shale
3045	3272	Shale & lime
3272	3492	Lime & shale
3492	3496	Sand
	3496	Rotary Total Depth

Spudded in @ 11:00 a.m. March 3, 1976. Cut 246' of 12 1/4" hole. Ran 6 jts. 8 5/8" casing, tallied 236.06'. Set @ 244.06'. Cemented with 165 sx. Sunset by Sun cement. Cement did circulate. Plug was down @ 3:30 p.m. March 3, 1976

Ran 106 jts. 4 1/2" casing, tallied 3502.88. Set @ 3491'. Cemented by Sun cement with 100 sx. Common, 10% salt followed by salt-flush. Plug was down @ 2:15 a.m. March 9, 1976.

SAMPLE TOPS:

Anhydrite 1667'
 B/Anhydrite 1696'

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Jerry A. Langrehr, Executive Vice President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the Nelson #3, SE NE SW Section 12-5S-22W Norton County, Kansas.



ABERCROMBIE DRILLING, INC.

By: Jerry A. Langrehr
 Jerry A. Langrehr - Exec. V.P.

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 16th day of March, 1976.

Diane Steincamp
 Diane Steincamp - Notary Public

My Commission Expires: February 18, 1980



15-137-20108-00-00



Kansas Corporation Commission

Joan Finney
Governor

Jim Robinson
Chairman

F. S. Jack Alexander
Commissioner

Rachel C. Lipman
Commissioner

Judith McConnell
Executive Director

Brian Moline
General Counsel

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION

February 5, 1992

R P Nixon Oper Inc
207 W 12th
Hays KS 67601

Nelson C 1
API 15-137-20,018
SE NE SW
Sec. 12-05-22W
Norton County

Dear Operator:


This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). Failure to do so is punishable by an administrative penalty of up to \$1000. If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,


David P. Williams
Production Supervisor

Conservation Division
William R. Bryson
Director

200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, Kansas 67202-1286
Telephone (316) 263-3238

District: #4 2301 E. 13th
Hays, KS 67601
(913) 628-1200