



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-137-00081-00-00

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name D. G. Hansen Trust,

Complete Address Box #187, Logan, Kansas.

Lease Name Hansen Well No. D-1

Location CSW-NW Sec. 26 Twp. 5 Rge. (E) (W) 21

County Norton Total Depth 3720'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Southwest Casing Pulling Company, Inc.,

Address Box #364, Great Bend, Kansas. License No. 399

Operation Completed: Hour 10:30 AM Day 29 Month 1 Year 1974

The above well was plugged as follows:

148'--10 3/4" Surface casing, cement circulated with 125 Sx. (9" Hole).

3717'--5 1/2" Production casing cemented on bottom with 350 Sx. Well plugged back to 3440'. Top perforations from 3422' to 3428'.

Sanded well back to 3400' and set 5 Sx. cement with dump bailer. Pulled 5 1/8" casing

and squeezed well initially with 5 sacks hulls and 15 sacks gel and followed with 150

Cu. Ft. cement fro 1075' to 750' then 20 sacks gel from 750' to 160' and finally 75

Cu. Ft. cement from 160' to bottom of cellar. Maximum pump-in pressure-200#. Final

shut-in pressure-100#.

INVOICED

I hereby certify that the above well was plugged as herein stated.

DATE 2/5/74  
INV. NO. 8507-W

Rec'D  
2-5-74

Signed: A. L. Pichela  
Well Plugging Supervisor