

DISTRICT CONSERVATION AGENT'S REPORT

TO:

15-137-00643-00-00

B

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____
LOCATION NW NW SE
SEC. 26 TWP. 5 RGE. 21W

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Dedrick

Operator Cranlyn Oil Co Address 310 KFH Bldg Wichita,

Field _____ County Norton

Total Depth 5700 Feet.

Plugging Contractor Barnes & Sons

Plugging Contractor's License No. 9

Address _____

(Describe briefly the manner in which the well was plugged)

8 5/8" at 250' circulated with cement-5 1/2" at 3682' with
70 sax cement behind.

Filled with sand to 3670', set 4 sax cement with dump bailer,
pulled 3200' 5 1/2", filled with mud to 260', set rock and
10 sax cement, mud to 35', set rock and 10 sax cement to
bottom cellar.

RECEIVED
STATE CORPORATION COMMISSION

JUL 21 1954

CONSERVATION DIVISION
Wichita, Kansas

Edna Lee
District Conservation Agent

Date 7-16-54

7-21-54

PLUGGING
FILE SEC 26 T 5 R 21W
BOOK PAGE 50 LINE 9