

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

API Number 15-137-00595-00-00

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Phillips Petroleum Co. (Paul Dean)

Complete Address Box 287 - Great Bend, Kansas 67530

Lease Name Kemper Well No. 3

Location NW 4 Sec. 26 Twp. 5 Rge. 21 (East) (West)

County Norton Total Depth 3683'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Phillips Petroleum Co.

Address Same as above License No. _____

Operation Completed: Hour: 2:00 PM Day: 28 Month: 6 Year: 1982

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

8 5/8" - 28# @ 426' w/ 300 sx circ 5 1/2" - 17# @ 3665'
w/ 150 sx - DV. tool @ 1848' w/ 12 sx (circ) - openhole 3665-83'
cast plug @ 3650' w/ 1 sx emt on top - Perfs 3464' to 3604'
Ordered 50 pozmix 6% gel - 32 cc - Pumped in 3 shells +
75 emt -> 14 sx gel -> 150 sx emt. S.I.P. 700#
Hook-up to 8 5/8" Pumped 3/4 BW - pressure to 700#

Amount of Surface Casing: 426'

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Dennis L. Hamel
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

RECEIVED
STATE CORPORATION COMMISSION

JUL 20 1982

CONSERVATION DIVISION
Wichita, Kansas

Signed: _____
Conservation Division Agent

INVOICED

DATE 7-22-82

INV. NO. 673-w