

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

15-137-00559-00-00

RECEIVED
STATE CORPORATION COMMISSION
FEB 5 1974
CONSERVATION DIVISION
Wichita, Kansas
2-5-74

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name D. G. Hansen Trust,

Complete Address Box #187, Logan, Kansas.

Lease Name Kemper Well No. 2

Location App:-SW-NW-NE Sec. 26 Twp. 5 Rge. (E) (W) 21

County Norton Total Depth 3642'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling Company, Inc.,

Address Box #364, Great Bend, Kansas. License No. 399

Operation Completed: Hour 12:00 M Day 29 Month 1 Year 1974

The above well was plugged as follows:

167'--8 5/8" Surface casing, cement circulated with 130 Sx.
3625'--5 1/2" Production casing cemented on bottom with 125 Sx. Open hole completion no
plug back nor perforations indicated.

Sanded well back to 3600' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing
and squeezed well initially with 5 sacks gel and 13 sacks gel and followed with 110 Cu.
Ft. cement from 1025' to 700' then 15 sacks gel from 700' to 180' and followed with
30 Cu. Ft. cement from 180' to 100' then 2 sacks gel from 100' to 25' and finally 10
Cu. Ft. cement from 25' to bottom of cellar. Maximum pump-in pressure-200#. Final
shut-in pressure-100#.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: H. L. Dechle
Well Plugging Supervisor

DATE 2/5/74

INV. NO. 8508-W