

R
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-137-00715-00-00

RECEIVED
STATE CORPORATION COMMISSION

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

JUL 7 1965
7-7-65
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Varn Petroleum Company,

Complete Address: 310 Sutton Place, Wichita, Kansas.

Lease Name Wiltrout Well No. 3

Location NE-SW-NE Sec. 27 Twp. 5 Rge. (E) (W) 21

County Norton Total Depth 3631

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Santa Fe Pipe and Supply, Incorporated,

Address: Box # 562, Great Bend, Kansas. License No. 574

Operation Completed: Hour 10:00AM Day 3 Month 7 Year 1965

The Above well was plugged as follows:

230'--8 5/8" Surface pipe, cement circulated.
3630'--5 1/2" Production casing. No perforations, No plug back.

Sanded well back to 3615' and set 5 Sx. cement with dump bailer. Pulled
5 1/2" casing to 555' and circulated heavy gel mud. (Used 20 Sx. gel).

Displaced 20 Sx. cement thru 5 1/2" @ 555'. Pulled 5 1/2" to 200' and displaced
20 Sx. cement thru 5 1/2". Pulled 5 1/2", set rock bridge @ 35' and 10 Sx.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Nichols
Well Plugging Supervisor

DATE 7/7/65

INV. NO. 1422-W