

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-137-00713-00-00

RECEIVED
STATE CORPORATION COMMISSION

APR 5 1966
4-5-66
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Varn Petroleum Company,
Complete Address: 502 Central Building, Wichita, Kansas.
Lease Name Kendrick Well No. 2
Location NE-NE-NW Sec. 27 Twp. 5 Rge. (E) (W) 21
County Norton Total Depth 3639
Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Santa Fe Pipe and Supply, Incorporated,
Address: Box # 562, Great Bend, Kansas. License No. 574
Operation Completed: Hour 10:00AM Day 1 Month 4 Year 1966

The Above well was plugged as follows:

214' -- 3 5/8" Surface pipe, cement circulated with 160 Sx.
3637 1/2" -- 5 1/2" Production casing cemented with 100 Sx. No plug, no perforations.

Sanded well back to 3625' and set 5 Sx. cement with dump bailer. Pulled
5 1/2" to 550' and circulated heavy gel mud. Pulled 5 1/2" to 490' and dis-
placed 20 Sx. cement thru 5 1/2". Pulled 5 1/2" to 210' and displaced 20 Sx.
cement thru 5 1/2". Pulled 5 1/2", set rock bridge @ 35' and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Dickel
Well Plugging Supervisor

INVOICED

DATE 4/5/66

INV. NO. 2985-W