

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-137-00712-00-00

RECEIVED
STATE CORPORATION COMMISSION

APR 5 1966

4-5-66

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Varn Petroleum Company,

Complete Address: 502 Central Building, Wichita, Kansas.

Lease Name Kendrick Well No. 1

Location SE-SE-NW Sec. 27 Twp. 5 Rge. (E) (W) 21

County Norton Total Depth 3603

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Santa Fe Pipe and Supply, Incorporated,

Address: Box # 562, Great Bend, Kansas. License No. 574

Operation Completed: Hour 10:00 Day 26 Month 3 Year 1966

The Above well was plugged as follows:

222'--8 5/8" Surface pipe, cement circulated with 175 Sx.
3600'--5 1/2" Production casing cemented with 100 Sx. No plug back, no per
forations.

Sanded well back to 3585' and set 5 Sx. cement with dump bailer.
Pull 5 1/2" to 550' and circulated heavy gel mud. (Used 18 Sx. gel). Pulled
5 1/2" to 490' and displaced 20 Sx. cement thru 5 1/2". Pulled 5 1/2" to 210' and
displaced 20 Sx. cement thru 5 1/2". Pulled 5 1/2" set rock bridge @ 35' and
10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: N. L. Nichols
Well Plugging Supervisor

DATE 4/5/66
INV. NO. 2986-4