

KANSAS

14

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-137-00554-00-00

RECEIVED
STATE CORPORATION COMMISSION
OCT 1 1969
CONSERVATION DIVISION
Wichita, Kansas
10-1-69

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Phillips Petroleum Company,

Complete Address Box #287, Great Bend, Kansas.

Lease Name Wil trout Well No. 3

Location Ne-Nw-SW Sec. 27 Twp. 5 Rge. (E) (W) 21

County Norton Total Depth 3657'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated _____

Plugging Contractor Knight Casing Pulling Company, Incorporated,

Address Box #105, Chase, Kansas. License No. 624

Operation Completed: Hour 3:30 PM Day 27 Month 9 Year 1969

The above well was plugged as follows:

433'--8 5/8" Surface casing, cement circulated with 300 Sx.
3657'--4 1/2" Casing cemented on bottom with 110 Sx. Top perforations from 3648 to 3651'.

Sanded well back to 3640' and set 3 Sx. cement with dump bailer. Pulled 4 1/2" casing
and squeezed well initially with 5 sacks hulls and 5 sacks gel and followed with 100
Sx. cement from 1125' to 1100' then 16 sacks gel from 1100' to 460' and followed with
20 Sx. cement from 460' to 380' then 9 sacks gel from 380' to 40' and finally 10 Sx.
cement from 40' to bottom of cellar. Maximum pump-in pressure-1500#. Final shut-in
pressure-100#. (Mudding and cementing operations by Allied Cementing Co., Inc.).

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 10/1/69

INV. NO. 564-W

Signed: W. L. Nichols
Well Plugging Supervisor