

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUL 31 1974

CONSERVATION DIVISION
Wichita, Kansas

7-31-74

15-137-20096-0000

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Thomas K. Travis,

Complete Address 348 North Roosevelt, Wichita, Kansas.

Lease Name Jacobs Well No. 1

Location SW-NW-SE Sec. 9 Twp. 5 Rge. (E) (W) 22

County Norton Total Depth 3560'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated _____

Plugging Contractor Indigo Drilling Company,

Address P. O. Box #83, Oberlin, Kansas. License No. _____

Operation Completed: Hour 9:30 PM Day 23 Month 7 Year 1974

The above well was plugged as follows:

80'--8 5/8" Surface casing, cement circulated with 110 Sx.

Circulated hole with heavy mud. Pulled DP to 900' and displaced 70 Sx. cement thru

DP. Pulled DP to 125' and displaced 20 Sx. cement thru DP. Pulled DP, set bridge @

40' wit' 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Geo. J. Massey
Well Plugging Supervisor

INVOICED

DATE 7/31/74
INV. NO. 9643-W