

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-137-20031-00-~~00~~
01

RECEIVED
STATE CORPORATION COMMISSION
NOV 3 1971
CONSERVATION DIVISION
Wichita, Kansas
11-3-71

Operator's Full Name Okmar Oil Company,

Complete Address 1130 Vickers KSB & T Building, Wichita, Kansas.

Lease Name Voss Well No. 1

Location SW-NE-SE Sec. 9 Twp. 5 Rge. (E) (W) 22

County Norton Total Depth 3566'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Knight Casing Pulling Company, Incorporated,

Address Box #405, Chase, Kansas. License No. 624

Operation Completed: Hour 11:30 AM Day 31 Month 10 Year 1971

The above well was plugged as follows:

263'--8 5/8" Surface casing, cement circulated.

3563'--5 1/2" Production casing cemented on bottom with 175 Sx. No plug back nor perforations indicated.

Sanded well back to 3550' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing (1020') and squeezed well initially with 5 sacks hulls and 17sacks gel and followed with 100 Sx. cement from 950' to 625' then 9 sacks gel from 625' to 275' and followed with 25 Sx. cement from 275' to 200' then 4 sacks gel from 200' to 30' and finally 10 Sx. cement from 30' to bottom of cellar. Maximum pump-in pressure-400#. Final shut-in pressure-200#. (Mudding and cementing performed by Halliburton Services).

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols
Well Plugging Supervisor

DATE 11/3/71
INV. NO. 4584-W