

10  
KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-137-00189-00-00

RECEIVED  
STATE CORPORATION COMMISSION

AUG 19 1963  
8-19-63  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Fender Pipe & Supply, Incorporated,  
Complete Address: Box # 202, Russell, Kansas.  
Lease Name Bullock Well No. 1  
Location NW-NE-NW Sec. 13 Twp. 5 Rge. (E) (W) 22  
County Norton Total Depth 3560'  
Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A       
Other well as hereafter indicated:       
Plugging Contractor: Barnes & Sons Pipe Pulling Co.,  
Address: 1450 Maple, Russell, Kansas. License No. 9  
Operation Completed: Hour 10:00AM Day 13 Month 8 Year 1963

The Above well was plugged as follows:

195'--8 5/8" Surface pipe, cement circulated. 5 1/2" cemented @ 3558' with 125 Sx.  
Top of perforations @ 3318'.

Sanded well back to 3305' and set 5 Sx cement with Dump bailer. Pulled 5 1/2"  
to 550' and circulated heavy gel mud. (25 Sx) and displaced 20 Sx cement  
thru 5 1/2".. Pulled 5 1/2" to 180' and displaced 20 Sx cement thru 5 1/2". Pulled  
5 1/2", set bridge @ 35' and 10 Sx cement to bottom of cellar. (Recovered 1410' 5 1/2".  
(Mudding and cementing operations performed by Globe Oil Well Cementing Inc.)

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 8/19/63  
INV. NO. 4592-W

Signed: H. L. Nichols  
Well Plugging Supervisor