

KANSAS

2
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-137-20087-0000

RECEIVED
STATE CORPORATION COMMISS IN
JUN 25 1970
CONSERVATION DIVISION
Wichita, Kansas
625-70

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Four-Way Operation, Incorporated,

Complete Address Box #698, Great Bend, Kansas.

Lease Name Stenger Well No. 1

Location NE-SE-SE Sec. 11 Twp. 5 Rge. (E) (W) 22

County Norton Total Depth 3591'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor G & G Drilling Company,

Address 1107 Union National Bank Building, Wichita, Ks. License No.

Operation Completed: Hour 6:30 PM Day 22 Month 6 Year 1970

The above well was plugged as follows:

211'--8 5/8" Surface casing, cement circulated.
Top of Dakota section @ 725'.

Circulated hole with heavy mud. Pulled DP to 940' and displaced 100 Sx. cement thru
DP from 940' to 615'. Pulled DP to 230' and displaced 20 Sx. cement thru DP from
230' to 170'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 6/25/70
INV. NO. 2121-u