

4-031633

12-17-91

14
R

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-137-20,109-0000

SANANE
4290 S2 W2 NE /4 SEC. 26, 05 S, 21 W
1320 3300 feet from S section line
1980 feet from E section line

Operator license# 5285 Lease Kemper well # 5

Operator: Dane G. Hansen Trust County Norton

Address: P.O. Box 187 Well total depth 3640 feet
Logan, Kansas 67646 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 208 feet

118.30

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cement Company License#

Address: Russell, Kansas 67665

Company to plug at: Hour: A.M. Day: 17 Month: December Year: 91

Plugging proposal received from: Harold Parsons

Company: D.G. Hansen Phone:

Were: Ordered 325 sks. 65/35 pozmix - 10% gel. - 500# hulls.
Allied Cement Company.
Perf. 1115' - 1800'. O.H. 3640' - 3642' - 4 1/2 open to T.D.

RECEIVED
KANSAS CORPORATION COMMISSION

JAN 13 1992

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 10:30A.M., Day: 17, Month: December, Year: 91

Actual plugging report: 8 5/8" @ 208' w/140 sks. 4 1/2" @ 3636' w/125
sks. O.H. Squeezed 4 1/2" w/225 sks. cement blend w/400# hulls.
Squeezed 8 5/8" w/100 sks. cement blend. Max. pressure on 4 1/2" -
400 P.S.I. Shut in @ 200 P.S.I. Max. pressure on backside - 300 P.S.I.
Shut in @ 150 P.S.I. Total sacks 325 cement.

Remarks:
Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO
Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO
Plugged through TUBING , CASING X. Elevation: GL

I did [X] / did not [] observe the plugging. Carl Goodrow

DATE 1-17-92

John S

(agent)

INV. NO. 34371