

4-031921

9-8-93  
15-137-20162-00-00  
API number: 15- -

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

NE SW NE /4 SEC. 26, 05 S, 21 W  
3630 feet from S section line  
1650 feet from E section line

Operator license# 6931

Lease Kemper well # 2

Operator: Bowman Oil Company

County Norton

Address: P.O. Box 17  
Codell, Kansas 67630

Well total depth 3650 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 202 feet

Aband. oil well X, Gas well, Input well, SWD, D &amp; A

Plugging contractor: Bill's Well Service License# 6997

Address: Codell, Kansas 67630

Company to plug at: Hour: P.M. Day: 8 Month: September Year: 93  
Completed April 26, 1994.

Plugging proposal received from: Don Bowman

Company: Bowman Oil Company

Phone:

Were: Order 200 sxs. 65/35 pozmix - 10% gel - 500# hulls.  
Allied Cement Company.  
Emergency plug with rig over the hole.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[ ], Part[ X ], None[ ]

Completed: Hour: 12:30 P.M., Day: 26, Month: September, Year: 94  
Completed April 24, 1994.

Actual plugging report: 8 5/8" set @ 202' w/200 sxs. cwc. 5 1/2" set @ 3649' w/150 sxs. D.V. @ 1800' w/400 sxs. Back off tubing 3110'.  
Pulled tubing to 1280' spotted 100 sxs. cement blend. Pulled tubing to 500' circulated cement blend to surface. Squeezed 5 1/2" with total of 170 sxs. cement blend to Max. P.S.I. 500#. Close in P.S.I. 200#. Backside not dug out and 8 5/8" cut and welded for squeeze collar until 4-26-94 when 8 5/8" was squeezed with 75 sxs. cement blend with 1/4# flocele per sx. to Max. P.S.I. 300#. Closed in at 50# P.S.I.

Remarks:

Condition of casing(in hole): GOOD BAD Anyh. plug: YES X NO  
Bottom plug(in place): YES, CALC X, NO Dakota plug: YES X, NO  
Plugged through TUBING X, CASING. Elevation: GL

I did[X] / did not[ ] observe the plugging.

Carl Goodrow

(agent)

Form CP-2/3

RECEIVED  
STATE CORPORATION COMMISSIONMAY 13 1994  
5-13-94  
GL CONSERVATION DIVISION  
Wichita, Kansas

INVOICED

DATE 5-13-94

INV. NO. 404352 9-93