

4-041510

9-8

15-137-20102-00-00

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- -

NE SW NE /4 SEC. 26, 05 S, 21 W
3630 feet from S section line
1650 feet from E section line

Operator license# 6931

Lease Kemper well # 1

Operator: Bowman Oil Company

County Norton

Address: Box 17
Codell, Kansas 67630

Well total depth 3650 feet 118.62
Conductor Pipe: 5 1/2 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 200 feet
CWC.

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing, Inc. License#

Address: Russell, Kansas 67665

Company to plug at: Hour: 11:00A.M Day: 8 Month: September Year: 93

Plugging proposal received from: Don Bowman

Company: Bowman Oil Company Phone: 913-434-7202

Were: 5 1/2" casing set @ 3646' w/200 sxs. cement. O.H. @ 3646'-3650'.
Anhy. @ 1800' w/400 sxs. cement. 8 5/8" @ 200' w/200 sxs. cement.
5 1/2" @ 3646' w/150 sxs. cement. Ordered 100 sxs. cement plus ordered
150 sxs. 60/40 pozmix - 10% gel. with 1/4# F.C.

Plugging Proposal Received by: Dennis L. Hamel
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 1:00P.M., Day: 8, Month: September, Year: 93

Actual plugging report: Ran tubing to 1280' and spotted 100 sxs. common,
pulled to 500' and pumped in 50 sxs. cement circulated. Pulled tubing
out and tied onto 5 1/2" and pumped in 20 sxs. at 500#.

Remarks:
Condition of casing(in hole): GOOD BAD X Anhy. plug: YES X NO
Bottom plug(in place): YES , CALC X, NO Dakota plug: YES X, NO
Plugged through TUBING X, CASING . Elevation: GL

I did observe the plugging.

Dennis L. Hamel
(agent)
Form CP-2/3
Rec'd 10-4-93
MT

INVOICED
DATE OCT 05 1993
INV. NO. 38874
9-8