

15-137-00558-00-00 138  
2-18-88 R

6 031039

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 1960  
NW NW NE SEC. 26, T 5 S, R 21 W/E  
4950 feet from S section line  
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5258

Lease Name Kemper Well # 1  
County Norton 118.37  
Well Total Depth 3642 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 158

Operator: D. G. Hansen Trust  
Name & Address Box 187  
Logan, Kansas 67646

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Allied Cement Co. License Number  
Address Plainville, Ks.

Company to plug at: Hour: AM Day: 18 Month: Feb Year: 19 88

Plugging proposal received from Johnnie Parsons  
(company name) Hansen Trust (phone)

were: 8 5/8" set at 158' w/135 sks cwc. 5 1/2" set at 3639' w/100 sks.

5 1/2" squeezed at 1366' w/280 sks. Open hole 3620' - 3642'. Order 200 sks ATL  
Cement Blend 65/35 Poz 10% Gel 2% Dical 5 sks Hulls. Allied Cement Co.

OWS Water truck and company truck.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 11:45AM Day: 18 Month: Feb Year: 19 88

ACTUAL PLUGGING REPORT Squeezed 5 1/2" w/150 sks Cement Blend w/4 sks Hulls mixed

into Max Psi 1000#. Close in Psi 600#. Squeezed 8 5/8" - 5 1/2" Annulus w/50 sks Cement  
Blend w/1 sk Hulls mixed in. To max Psi 400#. Close in 200# STATE PLUG COMPLETE.

RECEIVED  
STATE CORPORATION COMMISSION  
4-22-88  
APR 22 1988

Remarks: (if additional description is necessary, use BACK of this form.)

Observe this plugging.

NOTICED  
4-26-88  
a. 20451

Signed Carl Goodrow (TECHNICIAN)