

JUN 29 2000
6-29-2000

4-032423

CONSERVATION DIVISION
Wichita, Kansas

15-137-01001-000
API Number: 15- - 1958

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

SW NW NE /4 SEC. 27, 05, 21 W
4290 feet from S section line
2310 feet from E section line

Operator license# 5252

Lease: Wilttrout Well # 7

Operator: R.P. Nixon Operations, Inc.

County: Norton 116.61

Address: 207 West 12th Street
Hays, Kansas 67601

6/5

Well total depth 3588 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 217 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: R.P. Nixon Operations, Inc. License# 5252

Address: 207 West 12th Street - Hays, Kansas 67601

Company to plug at: Hour: A.M. Day: 05 Month: June Year: 2000

Plugging proposal received from: Paul Nixon

Company: R.P. Nixon Operations, Inc. Phone: -

Were: Order 300 sxs 60/40 pozmix - 10% gel - 400# hulls.
Allied Cement Company.
Order workstring.
TA#4-001,836

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All , Part , None

Completed: Hour: 11:00 A.M. , Day: 5 Month: June , Year: 2000

Actual plugging report: 8 5/8" set at 217'w/NA sxs. 5 1/2" set at 3585' w/N.A. sxs.
O.H. 3585' - 3588'. Ran tubing to 1900' - displaced 100 sxs cement blend. Pulled tubing to 1000' - circulated cement blend with 80 sxs with 400# hulls mixed in. Tied onto 5 1/2" - squeezed with total of 200 sxs cement blend to Max. P.S.I. 300#. Squeezed 8 5/8" with 50 sxs cement blend. 8 5/8" - 5 1/2" communicated. Plug complete.

Remarks:

Condition of casing(in hole): GOOD BAD Any plug: YES NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO
Plugged through TUBING , CASING . Elevation: _____ GL

I did / did not observe the plugging.

JUN 26 2000

INVOICED (agent) Carl Goodrow

HAYS, KS

DATE 7/5/00
WEL. NO. 106011

Form GP-2/3

