

6 030705

15-137-00550-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 1958

NEESE, SEC. 27, T 5 S, R 21 W

990 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5285

Lease Name WATKINS Well # 2

Operator: D. G. HANSEN

County NORTON 119.60

Name & Address Box 187

Well Total Depth 3680 feet

LOGAN, KANSAS

Conductor Pipe: Size feet

67646

Surface Casing: Size 8 5/8 feet 187

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor KELSO CASING PULLING License Number 6050

Address CHASE, KANSAS 67524

Company to plug at: Hour: PAM Day: 4 Month: 4 Year: 1986

Plugging proposal received from Tom

(company name) KELSO (phone)

were: 8 5/8 @ 187 w/150 sx. 5 1/2 @ 3670 w/125 sx. OPEN HOLE

ORDER SAND & COM. CMT. PULL PIPE ORDER 180 SX 60/40 26 GEL 300

40 SX. GEL 4 SX HULLS W.P. ALLIED CMT. CO.

STATE CORPORATION COMMISSION

413-86 APR 13 1986

CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 12:30 PM Day: 4 Month: 4 Year: 1986

ACTUAL PLUGGING REPORT Dump SAND FROM 3680' TO 3600' SPOT 5 SX. COM. CMT.

ON SAND w/BAILER NO PIPE RECOVERED. BRIDGE @ 2100'

MOVE ON RIG. RUN TUBING TO 2100' MIX. & Pump 250 SX.

CMT MIX. IN 2 STAGES LAYDOWN ALL TUBING. LOAD CASING

OPEN END. CMT. STAYED AT SURFACE

Hook ON TO BACK SIDE Pump CMT. PRESSURED TO 1000 # 1/4 BBL of em.

Remarks: Plug. COMPLETE

(If additional description is necessary, use BACK of this form.)

12
4-11-86

INVOICED

(did / did not) observe this plugging.

DATE APR 15 1986

Signed Carl Goodrow (TECHNICIAN)

INV. NO. 13440