

4-032422

API Number: 15-137-00208-0000
1956

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

NE NW NE _____/4 SEC. 27, 05, 21 W
4950 feet from S section line
1650 feet from E section line

Operator license# 5252

Lease: Wilttrout Well # 1
County: Norton 11/6.22

Operator: R.P. Nixon Operations, Inc.

Address: 207 West 12th Street
Hays, Kansas 67601 6/2

Well total depth 3576 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 192 feet

Aband. oil well X, Gas well _____, Input well _____, SWD _____, D & A _____

Plugging contractor: R.P. Nixon Operations, Inc. License# 5252

Address: 207 West 12th Street - Hays, Kansas 67601

Company to plug at: Hour: P.M. Day: 02 Month: June Year: 2000

Plugging proposal received from: Paul Nixon

Company: R.P. Nixon Operations, Inc. Phone: _____

Were: Order 300 sxs 60/40 pozmix - 10% gel - 500# hulls.
Allied Cement Company.
Order workstring. Pipe collapsed at 1085.
T.A. #4-001,831.

RECEIVED
KANSAS CORP COM
200 JUN 15 P 1:20
6-15-2000

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 11:35 A.M., Day: 2 Month: June, Year: 2000

Actual plugging report: 8 5/8" set at 192' w/NA sxs. 5 1/2" set at 3573' w/N.A. sxs.
O.H. 3573' - 3576'. PBTD 3050'. Ran workstring to bridge at 1085' - circulated cement blend
to surface. Tied onto 5 1/2". Squeezed with total of 250 sxs cement blend with 300# hulls
mixed into Max. P.S.I. 500#. Squeezed 8 5/8" with 50 sxs cement blend to Max. P.S.I. 300#.
Plug complete.

Remarks: _____

Condition of casing (in hole): GOOD _____ BAD _____ Anhy. plug: YES X NO _____
Bottom plug (in place): YES _____, CALC _____, NO _____ Dakota plug: YES X, NO _____
Plugged through TUBING _____, CASING _____ Elevation: _____ GL

I did [X] / did not [] observe the plugging.

Carl Goodrow
(agent)

INVOICED P.
DATE 6/16/00
REL. NO. 61877

Form CP-273

