

5-3

4-032058

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 S. MARKET, ROOM #2078
WICHITA, KANSAS 67202

API number: 15-137-20,091 ⁰⁰⁻⁰⁰
SE SW NE /4 SEC. 11, 05 S, 22 W
2970 feet from S section line
1650 feet from E section line

Operator license# 5252 Lease Stenger well # A-2

Operator: R.P. Nixon Operations County Norton

Address: 207 W. 12th Street Well total depth 3500 ^{113.75} feet
Hays, Kansas 67601 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 276 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cement Company License# -

Address: Hays, Kansas 67601

Company to plug at: Hour: P.M. Day: 3 Month: May Year: 95

Plugging proposal received from: Paul Nixon

Company: R.P. Nixon Operations Phone:

Were: Order 225 sxs. 60/40 pozmix - 10% gel - 500# hulls.
7 sxs. gel - 500# hulls.

STATE CORPORATION COMMISSION
MAY 19 1995
S-19-95
WICHITA, KANSAS

Plugging Proposal Received by: Carl Goodrow
Plugging operations attended by agent? All[], Part[X], None[]

Completed: Hour: 6:30P.M., Day: 3, Month: May, Year: 95

Actual plugging report: 8 5/8" set @ 276' w/140 sxs. cwc. 4 1/2" set at 3499' w/125 sxs. Critical area control shots at 990' - 1740'. Squeezed 8 5/8" w/10 sxs. Max. P.S.I. 500#. Close in P.S.I. 500#. Squeezed 4 1/2" w/25 sxs. cement blend with 200# hulls - followed by 7 sxs. gel spacer - followed by 150 sxs. cement blend w/300# hulls mixed in to Max. P.S.I. 1200#. Close in P.S.I. 500#. Plug complete.

Remarks:
Condition of casing(in hole): GOOD X BAD Anhy. plug: YES 1675 NO
Bottom plug(in place): YES , CALC X, NO Dakota plug: YES X, NO
Plugged through TUBING , CASING X. Elevation: 2073 GL

I did X / did not observe the plugging. Carl Goodrow
(agent)

INVOICED
DATE 5-24-95
SER. NO. 42891