

4-031982

9-28

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-137-20,235 ⁰⁰⁻⁰⁰

SW NW NE /4 SEC. 12, 05 S, 22 W
4290 feet from S section line
2310 feet from E section line

Operator license# 5252

Lease Boyd well # 1

Operator: R.P. Nixon Operations, Inc.

County Norton

Address: 207 West 12th Street
Hays, Kansas 67601-3898

Well total depth 3510 feet ^{114.07}
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 185 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Jay-Lan Corporation License# 5128

Address: Hays, Kansas 67601

Company to plug at: Hour: A.M. Day: 28 Month: September Year: 94

Plugging proposal received from: Paul Nixon

Company: R.P. Nixon Operations, Inc. Phone: _____

Were: Order 250 sxs. 60/40 pozmix - 10% gel.
Allied Cement Company.
Order work string of 2 3/8" tubing.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[], Part[], None[]

Completed: Hour: 11:30A.M., Day: 28, Month: September, Year: 94

Actual plugging report: 8 5/8" set @ 185' w/130 sxs. 4 1/2" set at
3509' w/125 sxs. Prod. perfs. 3366' - 3486'. P.B.T.D. 2986' sand.
Ran tubing to 1701'. Pumped 50 sxs. cement blend w/100# hulls. Pulled
tubing to 700'. Pumped 50 sxs. cement blend w/100# hulls - cement
circulated. Pulled tubing. Squeezed 4 1/2" with total 200 sxs. cement
w/200# hulls to Max. P.S.I. 200#. Close in P.S.I. 200#. Squeezed
8 5/8" with 50 sxs. cement blend to Max. P.S.I. 300#. Close in P.S.I.
300#. Plug complete.

Remarks:

Condition of casing(in hole): GOOD BAD Anhy. plug: YES NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO
Plugged through TUBING , CASING . Elevation: _____ GL

I did did not observe the plugging.

Carl Goodrow
(agent)

INVOICED

DATE 10-7-94

INV. NO. 41362
9-28 DEC 12 1994

RECEIVED
STATE CORPORATION COMMISSION
Form CP-2/3
OCT 07 1994
10-7-94
WICHITA, KANSAS