

4-031659

2-4

10
R

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-137-20,108 -00-00

SE NE SW /4 SEC. 12, 05 S, 22 W
1650 feet from S section line
2970 feet from E section line

Operator license# 5252

Lease Nelson well # 1

Operator: R.P. Nixon Operations, Inc.

County Norton

Address: 207 W. 12th Street
Hays, Kansas 67601

Well total depth 3493 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 236 feet

113.52

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Jay Lan Corporation License# 5128

Address: Hays, Kansas 67601

Company to plug at: Hour: P.M. Day: 4 Month: February Year: 92

Plugging proposal received from: Paul Nixon

Company: R.P. Nixon Phone: _____

Were: 8 5/8" set @ 236' cwc. 4 1/2" set @ 3488' w/100 sx.
Top perf. 3376'. Order 415 sx. 65/35 pozmix - 10% gel. - 500# hulls.
B.J. Services.

Plugging Proposal Received by: Carl Goodrow
Plugging operations attended by agent? All[], Part[], None[]

3-9-92

Completed: Hour: 3:00P.M., Day: 4, Month: February, Year: 92

Actual plugging report: Shots @ 1664' and 950'. Hole @ 3042'. Ran tubing to 1660' circ. cement. Laid down tubing, squeezed 4 1/2" w/total 135 sx. cement blend w/100# hulls to max. P.S.I. 1050#. Close in P.S.I. 1050#. Cement to 3400'. 8 5/8" squeezed w/30 sx. cement to max. P.S.I. 500#. Close in P.S.I. 500#. Plug complete.

Remarks: _____
Condition of casing(in hole): GOOD BAD Any plug: YES NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO
Plugged through TUBING , CASING . Elevation: 2074 GL

I did did not observe the plugging. Carl Goodrow

DATE 3-12-92

INV. NO. 34730

(agent)