

8-15

4-061097

D-19,440

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-137-20093-00-01
NW SW SE /4 SEC. 11, 05 S, 22 W
990 feet from S section line
2310 feet from E section line

Operator license# 6009
Operator: Double Eagle Exploration
Address: 800 W.47th St. Ste. #318
Kansas City, MO 64112

Lease: Stenger Well # 3
County: Norton 53.95
Well total depth 1660 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 7 5/8 Inch @ 270 feet

Aband. oil well, Gas well, Input well, SWD X, D & A

Plugging contractor: Co Tools License#

Address:

Company to plug at: Hour: 10:00 A.M. Day: 14 Month: August Year: 1997

Plugging proposal received from: Pat Walters

Company: Double Eagle Exploration, Inc. Phone: 816-531-0202

Were: Order 250 sxs common w/3% c.c.
Planned to squeeze casing to repair. Decided to plug.
Emergency permission to plug with rig over hole.

RECEIVED
OCT 20 1997
11:29 AM


Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All [], Part [], None [X]

Completed: Hour: 9:30 A.M., Day: 15, Month: August, Year: 1997

Actual plugging report: 7 5/8" to 270' w/140 sxs. 4 1/2" to 3558' w/125 sxs. T.O.C. 2958'.
Squeezed granite wash perfs at 3534' - 3556' w/200 sxs. Perfs 3506' - 3510' and squeezed
with 200 sxs. Perfs 1650' - 1660' and squeezed with 400 sxs. Perfs 945' - 952' and squeezed
with 200 sxs. Perfs 740' - 748' and circulated cement with 400 sxs. Perfs for disposal at
1265' - 1380'. Cleaned out to perfs. Casing bad from 500' on down. Ran tubing to top of
perfs. Pumped 100 sxs cement. Tubing stuck. On August 15, 1997, cut tubing off at 700'.
Circulated cement to surface and pulled tubing. Tied onto casing and squeezed to 500# S.I.P.
Used 75 sxs for a total of 175 sxs to plug the well.

Remarks: Allied Cementing.
Condition of casing(in hole): GOOD BAD X Anhy.plug: YES X NO
Bottom plug(in place): YES X, CALC, NO Dakota plug: YES X, NO
Plugged through TUBING X, CASING. Elevation: 2089 GL

I did [] did not [X] observe the plugging.


OK (agent)

Form CP-2/3

INVOICED
DATE 8-30-97
INV. NO. 48827
8-15

OCT 30 1997