

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-21099-00-00
Spot: NESWSW Sec/Twnshp/Rge: 30-17S-9W
840 feet from S Section Line, 4440 feet from E Section Line
Lease Name: MOLLHAGEN Well #: 4
County: ELLSWORTH Total Vertical Depth: 3207 feet

Operator License No.: 31528
Op Name: KELSO, MIKE - OIL, INC.
Address: PO BOX 467
CHASE, KS 67524

CIBP Size: feet: 3199
PROD Size: 4.5 feet: 3203 150 SX CMT
SURF Size: 8.625 feet: 280 185 SX CMT

\$104²³

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/13/2004 3:15 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: Sand perms to 3100' and put 4 sxs cement on top; cut off 4-1/2" casing; pull to 1225' and pump 35 sxs; pull to 900' and pump 35 sxs; pull to 330' and circ to surf.

RECEIVED
KCC DISTRICT #2
DEC 17 2004

Plugging Proposal Received By: VIRGIL CLOTHIER
Date/Time Plugging Completed: 12/13/2004 5:15 PM

Witness Type: PARTIAL
KCC Agent: VIRGIL CLOTHIER

WICHITA, KS

Actual Plugging Report:

Sanded perforations to 3100' and put 4 sacks of cement on top. Attempted to determine amount of stretch; parted 4-1/2" casing at 950'. Pulled to 900' and pumped 70 sacks of cement. Pulled to 330' and circulated cement to surface.

Allied Cement #20148
60/40 posmix with 4% gel.

Perfs:

Top	Bot	Thru	Comments
3194	3198		

RECEIVED
DEC 23 2004
KCC WICHITA

Remarks:

Plugged through: CSG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

INVOICED
DATE 12.27.04
INV. NO. 2005060947