

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-053-01131-00-00  
Spot: SESESW Sec/Twnshp/Rge: 34-16S-10W  
330 feet from S Section Line, 2970 feet from E Section Line  
Lease Name: PHILLIPS Well #: 2  
County: ELLSWORTH Total Vertical Depth: 3272 feet

Operator License No.: 30458  
Op Name: RJM COMPANY  
Address: PO BOX 256  
CLAFLIN, KS 67525

PROD Size: 5.5 feet: 3261 200 SX CMT  
SURF Size: 8.625 feet: 362 200 SX CMT

#10634

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/16/2004 9:30 AM  
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.  
Proposal Rcvd. from: BRIAN SCHUMACHER Company: D S & W WELL SERVICING, INC. Phone: (620) 587-3361

Proposed Plugging Method: See actual report.

RECEIVED  
KCC DISTRICT #2  
DEC 17 2004  
WICHITA, KS

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: PARTIAL  
Date/Time Plugging Completed: 12/16/2004 11:00 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Sanded bottom perforations to 3100' and set CIBP at 3050'. Perforated at 1300', 1000', and 412'. Ran tubing to 1300' and pumped 35 sacks of cement. Pulled tubing to 1000' and pumped 35 sacks of cement. Pulled to 412' and circulated cement to surface.

Copeland Cement #25778

60/40 posmix with 4% gel.

Perfs:

RECEIVED  
DEC 23 2004  
KCC WICHITA

Remarks:

Plugged through: TBG

District: 02

Signed Virgil Clothier  
(TECHNICIAN)

INVOICED

DATE 12-22-04  
INV. NO. 2005060969