

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-137-20101-00-00
Spot: CN2NENE Sec/Twnshp/Rge: 26-5S-21W
4950 feet from S Section Line, 660 feet from E Section Line
Lease/Unit Name: KEMPER Well Number: 4
County: NORTON Total Vertical Depth: 3590 feet

Operator License No.: 5252
Op Name: NIXON, R P OPERATIONS, INC
Address: 207 W 12TH
HAYS, KS 67601

Conductor Pipe: Size feet: \$114.08
Surface Casing: Size 8.625 feet: 200 140 SX CMT
Production: Size 4.5 feet: 3590 125 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 03/13/2002 10:00 AM
Plug Co. License No.: 5252 Plug Co. Name: NIXON, R P OPERATIONS, INC
Proposal Rcvd. from: PAUL NIXON Company: NIXON, R P OPERATIONS, INC Phone: (785) 628-3834

Proposed Plugging Method: Ordered out 240 sxs 60/40 pozmix - 10% gel - 500# hulls.
Tubing and rods stuck at 1365'.
Ran tubing to top of fish.

Plugging Proposal Received By: HERB DEINES Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 03/13/2002 12:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Express Well Service ran tubing to 1295'.
Allied pumped 80 sxs 60/40 pozmix - cement circulated.
PTOH. Allied squeezed 110 sxs with 400# hulls.
Max. P.S.I. 1000#. S.I.P. 400#.
Hooked up to backside and pumped 50 sxs cement with 100# hulls.
Max. P.S.I. 300#. S.I.P. 200#.

RECEIVED
MAR 21 2002
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Richard Williams
(TECHNICIAN)

INVOICED

DATE 3-22-02

INV. NO. 2002061557

Form CP-2/3

MAR 18 2002

