

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-137-00560-00-00
Spot: CNENWNE Sec/Twnshp/Rge: 26-5S-21W
4950 feet from S Section Line, 1650 feet from E Section Line
Lease/Unit Name: KEMPER Well Number: 3
County: NORTON Total Vertical Depth: 3622 feet

Operator License No.: 5252
Op Name: NIXON, R P OPERATIONS, INC
Address: 207 W 12TH
HAYS, KS 67601

Conductor Pipe: Size feet: 3117.72
Surface Casing: Size 8.625 feet: 155
Production: Size 5.5 feet: 3604
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 03/14/2002 8:00 AM
Plug Co. License No.: 5252 Plug Co. Name: NIXON, R P OPERATIONS, INC
Proposal Rcvd. from: PAUL NIXON Company: NIXON, R P OPERATIONS, INC Phone: (785) 628-3834

Proposed Plugging Method: Ordered out 300 sxs 60/40 pozmix - 10% gel - 500# hulls.
Fluid level 2800' from surface.
No squeeze records.
Perforate Anhydrite at 1775' and Dakota Base at 1100'.

Plugging Proposal Received By: HERB DEINES Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 03/14/2002 9:00 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perf Tech perforated anhy. at 1775' and Dakota at 1100'.
Allied pumped 250 sxs 60/40 pozmix - 10% gel with 400# hulls.
Max. P.S.I. 600#. S.I.P. 350#.
Hooked up to backside - pumped 50 sxs 60/40 pozmix - 10% gel with 100# hulls.
Max. P.S.I. 100#. S.I.P. 100#.

RECEIVED
MAR 21 2002
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

HO

Signed

Richard Williams
(TECHNICIAN)

MAR 18 2002

INVOICED

Form CP-2/3

DATE 3-22-02

INV. NO. 2002061557

D G HANSEN

#3 KEMPER

26-5-21W
NE NW NE

Contr. C-G DRILLING

NORTON

County

R. 2190 RB Comm.

Comp. 9-9-60

IP 32 BOPD

Tops	Depth	Datum
ANH	1778	+412
HFEB	3329	-1139
TOR	3356	-1166
KC	3372	-1182
B/KC	3560	-1370
ARB	3602	-1412
TD	3622	-1432

Casing

8" 155

5" 3604

ACID 1500

RAY WEST POOL

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS