

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-137-00545-00-00  
Spot: CSWNWSW Sec/Twnshp/Rge: 26-5S-21W  
1650 feet from S Section Line, 4950 feet from E Section Line  
Lease/Unit Name: FEE E Well Number: 1  
County: NORTON Total Vertical Depth: 3677 feet

Operator License No.: 5252  
Op Name: NIXON, R P OPERATIONS, INC  
Address: 207 W 12TH  
HAYS, KS 67601

Conductor Pipe: Size feet: 8 1/2  
Surface Casing: Size 8.625 feet: 160  
Production: Size 5.5 feet: 3667  
Liner: Size feet:

Well Type: OIL UTC Docket No: Date/Time to Plug: 03/14/2002 9:30 AM

Plug Co. License No.: 5252 Plug Co. Name: NIXON, R P OPERATIONS, INC

Proposal Rcvd. from: PAUL NIXON Company: NIXON, R P OPERATIONS, INC Phone: (785) 628-3834

Proposed Plugging Method: Ordered out 350 sxs 60/40 pozmix - 10% gel - 500# hulls.  
Fluid 2500' from surface.  
No squeeze records. Perforate Anhydrite at 1850' and Dakota Base at 1175'.

Plugging Proposal Received By: HERB DEINES

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 03/14/2002 10:30 AM

KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perf Tech perforated anhydrite at 1850' and Dakota at 1175'.  
Allied pumped 325 sxs 60/40 pozmix - 10% gel with 500# hulls.  
Max. P.S.I. 500#. S.I.P. 250#.  
Hooked up to backside 700# instant - cement in cellar.  
(Cement in cellar indicates squeeze.)

RECEIVED  
MAR 21 2002  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

Richard Williams

(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 3-22-02

INV. NO. 2002061557

MAR 18 2002

D G HANSEN

#1 FEE 'E'

26-5-21W  
SW NW SW

Contr. C-G DRLG

NORTON County

E 2255RB Comm. 8-8-59

Comp. 11-6-59

IP

25 BOPD

Tops	Depth	Datum
ANH	1835	+420
TOP	3228	-973
NEEB	3394	-1139
TOR	3419	-1164
LANS	3437	-1182
B/KC	3623	-1368
ARB	3665	-1410
TD	3677	-1422

Casing

8" 160

5" 3667

CO 3677: ACID 500

RAY WEST POOL


INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS

1150