

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-137-18172-00-00  
Spot: S2NESE Sec/Twnshp/Rge: 27-5S-21W  
1650 feet from S Section Line, 660 feet from E Section Line  
Lease/Unit Name: WILTROUT Well Number: 8  
County: NORTON Total Vertical Depth: 3671 feet

Operator License No.: 5252  
Op Name: NIXON, R P OPERATIONS, INC  
Address: 207 W 12TH  
HAYS, KS 67601

Production Casing Size: 4.5 feet: 3671  
Surface Casing Size: 8.625 feet: 192

#11931

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/18/2003 10:00 AM  
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS  
Proposal Rcvd. from: PAUL NIXON Company: NIXON, R.P. OPERATIONS, INC. Phone: (785) 628-3834

Proposed Plugging Method: Ordered out 250 sxs 60/40 pozmix - 10% gel - 800# hulls.  
Squeeze 2450' - 2483'.  
Retreivable bridge plug at 3404' with sand on top.

Plugging Proposal Received By: HERB DEINES Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 09/18/2003 3:00 PM KCC Agent: RICHARD WILLIAMS

**Actual Plugging Report:**

Ran tubing to 3000'.  
Allied pumped 75 sxs 60/40 pozmix - 10% gel - neat.  
Pulled tubing to 2000'.  
Allied pumped 60 sxs cement with 400# hulls - cwc.  
PTOH. Allied squeezed with 10 sxs cement.  
Max. P.S.I. 900#. S.I.P. 700#.  
Hooked up to backside.  
Allied pumped 105 sxs cement with 100# hulls.  
Max. P.S.I. 300#. S.I.P. 100#.

RECEIVED  
SEP 23 2003  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY. EMERGENCY PLUG ORDERES WITH RIG OVER HOLE.

Plugged through: TBG

District: 04

HD.

Signed

*Richard Williams*

(TECHNICIAN)

INVOICED

DATE 9.23.03

INV. NO. 2004060536

Form CP-2/3

SEP 22 2003

JOCELYN-VARM

#8 WILTROUT

27-5-21W

SL NE SE

Contr. TRUSCO DRLG

NORTON County

E 22 1/2 RB Comm.

Comp. 8-21-59 IP

250 BOPD

Tops	Depth	Datum
HEEB	3379	-1137
TOR	3407	-1165
LANS	3422	-1180
ARB	3653	-1411
REAG	3668	-1426
TD	3671	-1429

Casing  
 8" 192  
 4" 3671  
 DST 3656-3671/1 HR, 2076' FR O,  
 NW, BHP 805#  
 PERF 1/3647-48: PLUG 3615: SWB  
 71 BO/4 HR

RAY WEST POOL

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS