

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-137-00549-00-00

Spot: CNESWSE

Sec/Twnshp/Rge: 27-5S-21W

990 feet from S Section Line, 1650 feet from E Section Line

Lease/Unit Name: WATKINS

Well Number: 1

County: NORTON

Total Vertical Depth: 3635 feet

Operator License No.: 5252

Op Name: NIXON, R P OPERATIONS, INC

Address: 207 W 12TH  
HAYS, KS 67601

Conductor Pipe: Size

feet:

Surface Casing: Size 8.625

feet: 177

Production: Size 5.5

feet: 3631

Liner: Size

feet:

\$118.14

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 09/26/2001 9:00 AM

Plug Co. License No.: 5252

Plug Co. Name: NIXON, R P OPERATIONS, INC

Proposal Rcvd. from: PAUL NIXON

Company: NIXON, R P OPERATIONS, INC

Phone: (785) 628-3834

Proposed Plugging Method: Ordered out 325 sxs 60/40 pozmix - 10% gel.  
Well squeezed 2241' - 2273' w/300 sxs.  
Fluid Level 2830'.

Plugging Proposal Received By: HERB DEINES

WitnessType: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 09/26/2001 11:30 AM

KCC Agent: JAY PFEIFER

**Actual Plugging Report:**

Tied onto 8 5/8" - Instant pressure Max. 500#.  
Switched over to 5 1/2" and pumped 320 sxs with 300# hulls.  
Max. P.S.I. 1000#. S.I.P. 500#.

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

*Jay Pfeifer*

(TECHNICIAN)

RECEIVED

OCT 03 2001

KCC WICHITA

SEP 28 2001

INVOICE

DATE 1003-01

INV. NO. 2002060707


Form CP-2/3

D G HANSEN \_\_\_\_\_ #1 WATKINS \_\_\_\_\_ 27-5-21W  
 NE SW SE  
 Contr. C-G DRLG CO \_\_\_\_\_ NORTON \_\_\_\_\_ County  
 E 2218RB Comm. \_\_\_\_\_ Comp. 6-13-58 IP 25 BOPD

Tops	Depth	Datum
ANH	1800	418
HEEB	3356	-1138
TOR	3382	-1164
LANS	3400	-1182
B/KC	3587	-1369
ARB	3631	-1413
TD	3635	-1417

Casing  
 8" 177  
 5" 3631  
 DST 3498-3523/45", 18' M, w/  
 SPKS 0, BHP 845#  
 CO TD: TST 10 BOPH

RAY WEST POOL



INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS