

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-137-20125-00-00  
Spot: CNESWSW Sec/Twnshp/Rge: 12-5S-22W  
990 feet from S Section Line, 4290 feet from E Section Line  
Lease/Unit Name: ARCHER-NELSON Well Number: 4  
County: NORTON Total Vertical Depth: 3520 feet

Operator License No.: 30931  
Op Name: DAYSTAR PETROLEUM, INC.  
Address: 1321 W. 93 N.  
VALLEY CENTER, KS 67147

Conductor Pipe: Size feet: 314.40  
Surface Casing: Size 8.625 feet: 288 w/200 sxs cmt  
Production: Size 4.5 feet: 3519 w/100 sxs cmt  
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 08/01/2002 10:00 AM  
Plug Co. License No.: 30931 Plug Co. Name: DAYSTAR PETROLEUM, INC.  
Proposal Rcvd. from: ALAN WALKER Company: DAYSTAR PETROLEUM, INC. Phone: (620) 792-9490

Proposed Plugging Method: Ordered out 275 sxs 60/40 pozmix - 10% gel - 500# hulls.  
PBTB 3450'.  
Prod.Perfs 3434'-3436'; 3403'-3405'.  
Squeeze at 1987 - 1158' - 1190'.  
Fluid level 50'.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 08/01/2002 12:10 PM KCC Agent: RICHARD WILLIAMS

**Actual Plugging Report:**

Ran 2 3/8" tubing to 3430'.  
Allied pumped 50 sxs 60/40 pozmix - 10% gel with 200# hulls.  
Pulled tubing 2450'.  
Allied pumped 100 sxs with 300# hulls. Cement circulated.  
PTOH.  
Topped off with 20 sxs. No pressure. Casing leaks. Hole standing full of cement.  
Hooked up to backside. Pumped 50 sxs with 100# hulls.  
Max. P.S.I. 700#. S.I.P. 700#.

RECEIVED

AUG 05 2002  
8-5-2002  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Richard Williams  
(TECHNICIAN)

INVOICED

DATE 8-6-02

INV. NO. 2003060173

Form CP-2/3

AUG 01 2002

R.P. NIXON OPERATIONS  
207 W. 12TH ST.

#4 ARCHER-NELSON

12-5-22W  
NE SW SW

HAYS, KS. CTY NORTON

CONTR ABERCROMBIE DRLG., INC.

FIELD DENSMORE

GEOL \_\_\_\_\_  
E 2100 KB CM 3/21/78 CARD ISSUED 5/18/78 IP P 10 BOPD + WTR  
REAG 3519-27

+	+	+
+	+	+
+	+	+

API 15-137-20,125

SMP	TOPS	DEPTH	DATUM
TOP	3033	- 933	
HEEB	3229	-1129	
TQR	3253	-1153	
LANS	3271	-1171	
BKC	3458	-1358	
REAG SD	3518	-1418	
RID	3520	-1420	
DDTD	3527	-1427	

8-5/8" 288/200sx, 4 1/2" 3519/100sx  
NO LOG  
NO DST'S  
MICT - CO TD, DD 3527', SWB 2 BFPH,  
50% OIL, POP

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS