

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-19078-00-00  
Spot: SENESE Sec/Twnshp/Rge: 32-14S-13W  
1650 feet from S Section Line, 330 feet from E Section Line  
Lease Name: ROGG Well #: 5  
County: RUSSELL Total Vertical Depth: 2259 feet

Operator License No.: 6622

PROD Size: 7 feet: 2235 w/150 sxs cmt

Op Name: SCHOENBERGER, J.L. D/B/A JASON OIL

SURF Size: 10.75 feet: 650 w/350 sxs cmt

Address: PO BOX 701 363 W 12TH ST  
RUSSELL, KS 67665

# 73<sup>42</sup>

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 12/13/2004 9:00 AM

Plug Co. License No.: 31925

Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Rcvd. from: RICHARD MCINTYRE

Company: QUALITY WELL SERVICE, INC.

Phone: (620) 786-2001

Proposed  
Plugging  
Method:

Plugging Proposal Received By: CASE MORRIS

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 12/13/2004 4:00 PM

KCC Agent: CASE MORRIS

Actual Plugging Report:

Perfs:

Perforated at 650'.  
Ran tubing to 2000'.  
Pumped 10 sxs gel with 200# hulls followed with 65 sxs 60/40 pozmix - 10% gel cement with 100# hulls.  
Pulled to 1500' - pumped 130 sxs cement with 200# hulls.  
Pulled to 200' - circulated inside and out with 280 sxs cement.

Remarks: LEASE ORIGINALLY KNOWN AS ROGG #2. ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

18

Signed

*Case Morris*

(TECHNICIAN)

INVOICED

DATE 12-22-04

INV NO 2005060964

DEC 17 2004

CHAS. TRAPP

Renumbered #5  
#2

ROGG

32-14-13W  
SE NE SE

Contr.

RUSSELL

County

E 1701

Comm.

Comp.

1-4-52

IP

25 BOPD

Tops	Depth	Datum
TARK	2235	-534
T.D.	2259	-558

Casing

10" 650  
7" 2235

FL 30'

Csg Leak.

1600

HALL-GURNEY POOL

75x58  
500'

+	+	+
+	+	+
+	+	+

220  
2759

70x55 h. 1/2

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS

INDEXED